


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Ellis County, Sec. 15 Twp. 15 Rge. 16 (E) W (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines NW 1/4
Lease Owner The Carl Todd Drilling Company
Lease Name Schmidtberger Well No. 1
Office Address 101 KFH Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4-19-52 19
Application for plugging filed 2-21-52 19
Application for plugging approved 19
Plugging commenced 4-19-52 19
Plugging completed 4-19-52 19
Reason for abandonment of well or producing formation None

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3551 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
See Drillers Log Attached						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

filled hole with heavy mud to 2201, set plug. Cemented with 15 sacks, through drill pipe.
filled hole with mud to 35' set plug. Cemented with 10 sacks. Completed 10:45 a.m.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Carl Todd Drilling Company
Address 101 KFH Building, Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
APR 28 1952

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Carl Todd

(employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Carl Todd

101 KFH Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 21st day of April, 1952

My commission expires February 8, 1956 Notary Public.

PLUGGING
FILE SEC 15 T 15 R 16
BOOK PAGE 16 LINE 2

THE CARL TODD DRILLING COMPANY
 104 KPII Building,
 Wichita 2, Kansas

15.051 .00014.00.00

The Carl Todd Drilling Company, et al.
 Schridtberger No. 1
 NE NE NW 15-15-16W
 Ellis County, Kansas

Date Commenced: April 8, 1952
 Date Completed: April 19, 1952

Rotary Tools: 0' to 3551'

Elevation: 1913 R. B.

Casing Record:

8-5/8" 24# casing cemented at 240'
 With 175 sacks cement.

LOG		
0	45	Clay, rock
45	85	Shale
85	165	Shale, shells
165	195	Sand, shale
195	350	Sand rock, shale
350	494	Shale, shells
494	680	Sand
680	755	Shale, shells
755	1042	Rod bod, shells, iron
1042	1075	Anhydrite
1075	1355	Shale, shells
1355	1450	Shale, salt
1450	1500	Shale, salt
1500	1735	Shale, shells
1735	2010	Shale, lime
2010	2110	Lime, shale "candy"
2110	2975	Lime, shale
2975	3120	Lime
3120	3180	Lime, shale
3180	3202	Shale, lime
3202	3240	Lime
3240	3445	Lime
3445	3485	Congl.
3485	3504	Congl. (shale)
3504	3530	Arbuckle
3530	3551	Arbuckle - Total Depth

FORMATION TOPS	R.B.
Topoka	2925
Hoebner.	3117
Toronto.	3166
Lansing	3202
Shale Conglomerate	3447
Cht. Conglomerate	3462
Arbuckle.	3504
R. T. D..	3551

RECEIVED
 STATE CORPORATION COMMISSION
 APR 28 1952
 CONSERVATION DIVISION
 Wichita, Kansas

I, Carl Todd, do hereby certify that
 the above log is correct to the best
 of my knowledge and belief.

Carl Todd

PLUGGING
 FILE NO. 15-15-16W
 BOOK WELL LINE 26