


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County, Sec. 28 Twp. 14 Rge. (E) 20 (W)
Location as "NE/CNW/SW" or footage from lines SE SE NW
Lease Owner Herman Geo. Kaiser, Oil Producer
Lease Name Fisher Well No. 1
Office Address 710 909 Palace Bldg, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed June 15 19 57
Application for plugging filed June 15 19 57
Application for plugging approved June 15 19 57
Plugging commenced June 15 19 57
Plugging completed June 15 19 57
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3810 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	255	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded hole with heavy Rotary Mud to 600 ft. set plug and cemented with 25 sacks cement through drill pipe. Mudded hole to 40 ft. set plug and cemented with 10 sacks cement and 1/2 sack hulls to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30, Inc.
Address 710 Petroleum Bldg. Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
L. G. Sponenberg (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
(Address)

SUBSCRIBED AND SWORN TO before me this 21 day of June, 1957

My commission expires February 13, 1960

[Signature]
Notary Public.

PLUGGING
FILE SEC. 28 T. 14 R. 20W
BOOK PAGE 22 LINE 39

JUN 25 1957
CONSERVATION DIVISION
KANSAS

KANSAS GEOLOGICAL SOCIETY 15.051.01625.00.00
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS


COMPANY **H erman Geo. Kaiser, Oil Producer**

SEC. 28 T. 14 R. 20W
 LOC. SE SE NW $\frac{1}{4}$

FARM **Fisher** NO. **1**

COUNTY **Ellis**

TOTAL DEPTH **3810**
 COMM. **6/3/57** COMP. **6/15/57**
 SHOT OR TREATED
 CONTRACTOR **H-30, Inc.**
 ISSUED



CASING

20	10
15	8 255'
12	6
13	5

2101 DF
 ELEVATION 2104 KB
 PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

Top Soil & Rock	10
Post Rock	40
Shale	150
Shale with Iron Streaks	255
Blue Shale	480
Shale and Shells	778
Sand	1027
Shale and Shells	1385
Anhydrite	1423
Shale and Shells	1970
Shale with Lime Streaks	2045
Lime and Shale	2230
Lime	2290
Lime and Shale	2415
Lime (Sandy)	2500
Lime and Shale	3369
Kansas City Lime	3638
Lime and Shale	3715
Lime and Chert	3737
Cherty Lime and Shale	3780
Arbuckle	3793
Arbuckle and Reagan Sand	3810

FORMATION TOPS:

HEEBNER	3345'
TORONTO	3367'
LANSING	3386'
MARMATION CHERT	3690'
ARBUCKLE	3785'

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

By *C. P. Sproudy*

STATE OF KANSAS |
 | SS
 COUNTY OF SEDGWICK |

Subscribed and sworn to before me, a notary public, in and for said County and State this 21st day of June, 1957.

Rose Toney
 Notary Public

My Commission expires February 13, 1960.

PLUGGING
 FILE SEC. 28 T. 14 R. 20W
 BOOK PAGE 22 LINE 38

REL.
 STATE CORPORATION
 JUN 25 1957
 CONSERVATION DIVISION
 Wichita, Kansas