

15.051.01680.00.01

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____

LEASE NAME SchumacherWELL NUMBER #1 SWDSPOT LOCATION SE SE SWSEC. 21 TWP. 13S RGE. 20W (E) or (W) (W)COUNTY Ellis

Date Well Completed _____

Plugging Commenced 5-5-86Plugging Completed 5-5-86

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR K & E Drilling, Inc.ADDRESS 100 S. Main, 300 Hardage Ctr., Wichita, Ks. 67202PHONE # (316) 264-4301 OPERATORS LICENSE NO. 5266

Character of Well SWD
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YesWhich KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 1575'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	1574'	none
				2" Tub.	1100'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plug Job Only - No Pipe Recovery

Ran 125 sacks econolite w/2 sacks hulls down 2" tubing and 130 sacks econolite w/2 sacks hulls down backside.

Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) R. Darrell Kelso(Address) Box 347 Chase, Ks. 67524SUBSCRIBED AND SWORN TO before me this 7th day of May, 19 86

My Commission expires: _____



Notary Public

RECEIVED
STATE CORPORATION COMMISSION

MAY 08 1986

CONSERVATION DIVISION
Wichita, Kansas

15.051.01680.00.01

WELL NO.	1	D. A. Sabumacher	COMPANY	Gulf Oil Corporation	A.F.E.	3528
LEASE	1-4-55	Plugged	2-19-55	Well Plugged		
DATE—DRILLING BEGAN		WELL COMPLETED		FIRST PRODUCTION		
SAND RECORD	Plugged and Abandoned			TOTAL DEPTH		3622

CASING RECORD

SIZE	WEIGHT	THD.	CLASS	MAKE	SET AT DEPTH	BACKS CEMENT	LBS. CAL. CHLO.	PULLED	LEFT IN
5-5/8	*	*	*	*	1574	650		0	1574
5-1/2	14	82	42	Q2	3859	100		3196	663
* 2 Jct's - 32 - 10V - C-1 - IN									
32 Jct's - 23 - HT - A - SW									
1 Jct - 32 - 10V - C-1 - IN									
** 16 Jct's. CLASS C-1									
96 Jct's. CLASS A-EV									
2 Jct's. EV									

S- 21 T- 133 R- 200

[illegible]

ELEVATION— 12,000'

Distance II - 8' from NMB to top of 8-5/6" casing.

7rb. Part. 3052-3059: w/20 shots - treated w/250 gals IGA, fractured
w/1500 gals oil, 1500' med.

C
SE
of
SW

ALL INFORMATION CONTAINED
HEREIN IS UNCLASSIFIED

	From	To
Surface Clay	0	10
Shale & Shells		90
Hard Sand & Shale & Shells		985
Shale & Shells w/ sand streaks		1005
Sand & Shale		1320
Shale & Shells		1490
Hard Sand Shale & Shells		1565
Argillite		1617
Shale & Shells		1690
Shale & Limestone		2135
Limestone & Shale		2330
Limestone		2605
Limestone & Shale		3510
Limestone		3790
Limestone, Shale & Chert		3835
Cherty Limestone		3857
Argillite		3859
T.T. D.		3859

RECEIVED
STATE CORRUPTION COMMISSION

APR 14 1964

CONSERVATION UNION
Wichita, Kansas

PLUGGING
APR 20 21-13 20W
96 INC 29