

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

ELLIS County. Sec. 28 Twp. 15S Rge. 20 (E) W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW-SW-NW

Lease Owner BUFFALO-HOUSTON-RINE

Lease Name MUTUAL BUILDING AND LOAN Well No. 1

Office Address 320 CENTRAL BUILDING, WICHITA, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed 4-11-51 19

Application for plugging filed 4-11-51 19

Application for plugging approved 4-11-51 19

Plugging commenced 4-11-51 19

Plugging completed 4-11-51 19

Reason for abandonment of well or producing formation

NONE

If a producing well is abandoned, date of last production NONE 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES - VIA TELEPHONE - CONFIRMED VIA LETTER 4-12-51

Name of Conservation Agent who supervised plugging of this well ELDON PETTY - BOX 326, HAYS, KANSAS

Producing formation NONE Depth to top Bottom Total Depth of Well 4055 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|------------|---------|------|----|--------------------|--------|------------|
| WATER SAND | WATER | 40 | 75 | 12 $\frac{1}{2}$ " | 197' | CEMENTED |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

HEAVY MUD FROM TOTAL DEPTH TO 190'

PLUG @ 190' w/ 25 SACKS CEMENT

HEAVY MUD FROM PLUG @ 190' TO 30'

PLUG @ 30' w/ 25 SACKS CEMENT

RECEIVED
STATE CORPORATION COMMISSION

APR 19 1951

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to R. W. RINE DRILLING COMPANY, CONSERVATION DIVISION
Address 320 CENTRAL BUILDING, WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

E. H. SLOYER (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. H. Sloyer

320 CENTRAL BUILDING, WICHITA, KANSAS

SUBSCRIBED AND SWORN to before me this 18TH day of APRIL, 1951

My commission expires DECEMBER 29, 1952.

28-3278-s 4-50-10M

Notary Public.

PLUGGING
FILE SEC 28 T 15 R 20W
BOOK PAGE 25 LINE 7

MUTUAL WELL No. 1

SW SW NW
 SEC. 28-15-20
 ELLIS COUNTY,
 KANSAS

CONTRACTOR: THE R. W. RINE DRILLING COMPANY
 STARTED: MARCH 27, 1951

FINISHED: APRIL 11, 1951

LOG

| | | | | |
|----------------------------|------|---|------|---|
| SHALE | 0 | - | 320 | 12 1/2" Csg. AT 197' w/ 175 Sx. |
| SAND | 320 | - | 460 | SYFO @ 400' - OK |
| SAND AND SHALE | 460 | - | 585 | |
| SHALE AND SHELLS | 585 | - | 890 | |
| SAND | 890 | - | 990 | |
| SHALE AND SHELLS | 990 | - | 1290 | |
| SHALE AND SHELLS | 1290 | - | 1440 | |
| ANHYDRITE | 1440 | - | 1480 | |
| SHALE AND SHELLS | 1480 | - | 2330 | SYFO @ 1500' - 1° OFF |
| SHALE | 2330 | - | 2380 | |
| LIME | 2380 | - | 2815 | SYFO @ 2500 - OK |
| SHALE AND SHELLS | 2815 | - | 3000 | |
| LIME AND SHALE | 3000 | - | 3390 | |
| LIME | 3390 | - | 3860 | |
| LIME AND SHALE | 3860 | - | 3910 | |
| CHERTY LIME - SHALE - SAND | 3910 | - | 3938 | |
| CHERT - SAND | 3938 | - | 3949 | |
| CHERT AND LIME | 3949 | - | 3965 | |
| SAND AND CHERT | 3965 | - | 3982 | |
| SAND AND LIME | 3982 | - | 4007 | |
| SAND | 4007 | - | 4010 | |
| GRANITE WASH | 4010 | - | 4055 | T. D. - D & A HOLE PLUGGED W/ 25 SX. CEMENT @ 190' AND W/ 25 SX. @ 30'. |

STATE OF KANSAS)
) ss.
 COUNTY OF SEDGWICK)

I, E. H. SLOYER, DO HEREBY CERTIFY THAT THE ABOVE IS A TRUE AND ACCURATE LOG OF THE MUTUAL WELL No. 1, LOCATED IN SW, SW, NW OF SECTION 28, 15, 20 IN ELLIS COUNTY, KANSAS.

APR 19 1951
E. H. Sloyer
 SECRETARY

SUBSCRIBED TO AND SWORN BEFORE ME THIS 16TH DAY OF APRIL, 1951.

R. M. Green
 NOTARY PUBLIC

My Commission Expires December 29, 1952.

PLUGGING
 FILE SEC. 28 T. 15. R. 20 W.
 BOOK PAGE 73 LINE 7

STATE OF KANSAS

INVOICE

April 12, 1951 19

To: R. W. Rine Drilling Company
320 Central Bldg.
Wichita, Kansas

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

For: PLUGGING ASSESSMENT AS FOLLOWS:

Mutual Ins. Well No. #1
SW SW NW 28-15-20W
Ellis County
File No. 73-7

\$25.00

NOTE: We also need a Written Application, a Well Log and a Well Plugging Record on this well to complete our file.

4753
Paid
4-21-51
J.C. C-106

TO INSURE CORRECT APPLICATION KINDLY
RETURN PINK COPY WITH REMITTANCE



INVOICE

STATE CORPORATION COMMISSION
CONSERVATION DIVISION

APRIL 15 1921
R. W. RINE DRILLING COMPANY
320 CENTRAL BLDG

To:

320 BIRTING BUILDING

DETACH FROM CHECK AND RETAIN

THE R. W. RINE DRILLING CO.
320 CENTRAL BUILDING
WICHITA 2, KANSAS

No. 4753

For:

| DATE | GROSS | ADJUSTMENT | DISCOUNT | NET AMOUNT |
|--------|-------|------------|----------|------------|
| MAR 31 | 25.00 | | | 25.00 S- |

PAYMENT OF STATEMENT OR INVOICES

*Drilling: Mutual #1
SW & WNW
28-15-20 W
Ellis Co Kansas*

*12-15-21
R. W. Rine*

TO INSURE CORRECT APPLICATION KINDLY
RETURN PINK COPY WITH REMITTANCE