

WELL PLUGGING RECORD

STATE OF KANSAS STATE CORPORATION COMMISSION


Give All Information Completely Make Required Affidavit Mail or Bellver Report to: Conservation Division State Corporation Commission 800 Bittling Building Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

Ellis County Sec. 13 Twp. 15 Rge. (E) 20 (W) Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines SW SW NE Lease Owner G. W. Keyes Drilling Company etal Lease Name Penney Wann B Well No. 1 Office Address Ellinwood, Kansas Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole Date well completed Nov. 30, 1948 Application for plugging filed Sept. 20, 1949 Application for plugging approved Sept. 21, 1949 Plugging commenced Sept. 21, 1949 Plugging completed Sept. 25, 1949 Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production - - - - - 19 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty Producing formation - - - - - Depth to top - - - - - Bottom - - - - - Total Depth of Well 3708 Feet Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Rows include Surface Pipe and Long String.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from - - - - - feet to - - - - - feet for each plug set.

Filled hole with rock 3708 to 3695; dumped 5 sacks cement on bridge at 3695; mudded hole to 250', set rock bridge and dumped 20 sacks cement on bridge; mudded to 35', set rock bridge and cemented with 10 sacks, cement returning to base of cellar.

RECORDED

OCT 15 1949

STATE OF KANSAS COMMISSION

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to G. W. Keyes Drilling Co. Address Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. I. J. Rader (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) I. J. Rader

Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 13th day of October, 1949

My commission expires Feb. 10, 1951. George A. Meyer Notary Public.

PLUGGING FILE SEC 13 T 15 R 20W BOOK PAGE 115 LINE 26

WELL LOG

G. W. Keyes DRILLING COMPANY, et al, OWNERS - PENNEY WANN B #1
SW SW NE SECTION 13, Township 15, Range 20 W
Ellis County, Kansas

Elevation 2088 DF

Figures indicate bottom of formation
0 to 13 clay

Pipe Record:

8 5/8" set at 1322'
5 1/2" set at 3699'

27 sand
400 shale and shells

465 shale
490 sand

560 shale
620 sand

630 pyrite
665 shale

675 sand

950 shale and shells

990 sand

Tops, corrected 3' to derrick floor

Heebner shale 3334

Lansing 3387

Marmaton cherty lime 3670

Basal Sand 3697

1050 shale and shells

1313 Red bed

1318 Gypsum

1348 anhydrite

1485 red bed

Rotary commenced 11-9-48

completed 11-22-48

1680 shale and shells

1840 salt and shells

2060 shale and shells

Cable Tools commenced 11-26-48

completed 11-30-48

2385 lime and shale

2565 lime

2640 shale

2885 shale and shells

2950 shale

3060 shale and shells

3220 shale and lime

3410 lime and shale

3510 shale and lime

3600 lime

3655 lime and shale

3690 shale and lime

3695 lime

3699 shale

3701 sand

3701 Total Rotary Depth

CABLE TOOL WORK

Moved in Cable Tools, bailed hole, drilled cement and cleaned out hole to total Rotary Depth.

STATE OF KANSAS)
COUNTY OF BARTON) SS

I, G. W. Keyes, Part Owner, of the above-described well, being first duly sworn on oath declare: That I have knowledge of the facts, statements and matters herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

RECEIVED
Conservation Div.

PLUGGING
FILE SEC 13 T 15 R 20W
BOOK PAGE 115 LINE 26

Subscribed and Sworn to before me this 17th day of March, 1949.

G. W. Keyes
George A. Meyer
Notary Public

SEP 9 1949
STATE CORPORATION
COMMISSION

My commission expires Feb. 10, 1951