


DEC 16 1965

Form CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Ellis County, Sec. 11 Twp. 15S Rge. 20 ~~XXXXX(W)~~
Location as "NE/CNW/SW" or footage from lines SE SE NE
Lease Owner Rains & Williamson Oil Co.
Lease Name Rohr "A" Well No. 1
Office Address 1425 Wichita Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12/14/65 19
Application for plugging filed 12/13/65 19
Application for plugging approved 12/13/65 19
Plugging commenced 12/13/65 19
Plugging completed 12/14/65 19
Reason for abandonment of well or producing formation no oil or gas found
in commercial quantities
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker, Victoria, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3665 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1256'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug @ 540', spotted with 20 sx cement thru drill pipe;
mud back to 240', spotted with 20 sx cement; mud back to
40', set solid bridge @ 40', pumped in 20 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co.
Address 1425 Wichita Plaza, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wilson Rains, Partner ~~XXXXXX~~ (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
Wilson Rains 1425 Wichita, Plaza, WK
(Address)

SUBSCRIBED AND SWORN TO before me this 15 day of December, 1965

My commission expires July 25, 1968

Judith Caughlin
Judith Caughlin Notary Public.

OPERATOR: Rains & Williamson Oil Co.
Rohr "A" #1
SE SE NE Sec. 11-15S-20W
Ellis County, Kansas

CONTRACTOR: Rains & Williamson Oil Co.
COMMENCED: 12/2/65
COMPLETED: 12/14/65

REMARKS: Set 1256' of 8-5/8"
surface casing w 275 sx
common cement, 2% calcium
Chloride, and 225 sx GL3
cement.

FORMATIONS

Surface Clay	50'
Sand & Shells	500'
Shale & Sand	710'
Sand	917'
Shale & Red Bed	1000'
Shale	1237'
Anhydrite	1284'
Shale	1425'
Shale & Shells	1943'
Shale & Lime	2240'
Lime & Shale	2415'
Shale & Lime	2855'
Lime & Shale	2969'
Lime	3600'
Lime & Chert	3619'
Lime	3635'
Sand & Shale	3665'
Rotary Total Depth (D&A)	3665'

RECEIVED
STATE CORPORATION COMMISSION

DEC 16 1965

CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is true and
correct to the best of our knowledge
and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains
Wilson Rains

Subscribed and sworn to before me, a Notary Public in and for the State of
Kansas, County of Sedgwick, fifteenth day of December, 1965.

My Commission Expires:
July 25, 1968

Judith Caughlin
Judith Caughlin