

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Ellis County, Sec. 11 Twp. 15 Rge. 20 (E) (W)

Location as "NE/CNW&SW" or footage from lines NE NE NW
Lease Owner Deep Rock Oil Corporation
Lease Name Wann Well No. 1
Office Address Box 1051, Tulsa 2, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed December 20 19 54
Application for plugging filed January 3 19 55
Application for plugging approved _____ 19 _____
Plugging commenced December 23 19 54
Plugging completed December 23 19 54
Reason for abandonment of well or producing formation No shows

NORTH

Section Plat grid with 'X' in the top-left cell.

Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Patty, Hays, Kansas
Producing formation Reagan Depth to top 3701 Bottom 3706 Total Depth of Well 3712 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Rows include Reagan (Water, 3701-3706) and Below Dakota (Salt Water, 10 3/4, 970').

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3712-3522 80 sax common cement pumped thru drill pipe by Globe Cementers.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert & Jones
Address Orpheum Building, Wichita, Kansas

STATE OF Oklahoma, COUNTY OF Texas, ss. D. K. Auld (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 395, Tyrone, Oklahoma (Address)


SUBSCRIBED AND SWORN TO before me this 3rd day of January, 19 55

My commission expires May 27, 1955 [Signature] Notary Public.

PLUGGING
FILE SEC 11 T 15 R 20 W
BOOK PAGE 87 LINE 1

RECORDED
STATE CORPORATION COMMISSION
JAN 4 - 1955
CONSERVATION DIVISION
Wichita, Kansas

GABBERT-JONES DRILLING COMPANY
WICHITA, KANSAS
DRILLERS WELL LOG



W. C. WANN #1
NE NE NW, SEC. 11-15-20
ELLIS COUNTY, KANSAS
COMMENCED 12-9-54
COMPLETED 12-21-54

DEPTH		FORMATION	REMARKS
FROM	To		
0	550	SURFACE & SHELLS	
550	600	SHALE	
600	725	SHALE & SAND	
725	920	SHALE	
920	970	RED BED	RAN 970' OF 8 5/8" PIPE SET @ 970' w/400 SACKS CEMENT.
970	1150	SHALE & SHELLS	
1150	1285	RED BED	
1285	1335	ANHYDRITE	
1335	1555	SHALE & LIME SHELLS	
1555	1800	SHALE & SHELLS	
1800	2225	SHALE & LIME	
2225	2590	LIME	
2590	2680	LIME & SHALE	
2680	2965	SHALE & SHELLS	
2965	3115	SHALE	
3115	3215	SHALE & LIME	
3215	3617	LIME	
3617	3650	LIME & SHALE	
3650	3674	SHALE & CHIRT	
3674	3682	CONGLOMERATE	
3682	3689	SAND	
3689	3712	SAND & CHIRTY QUARTZITE	
3712	TD		DRY AND ABANDONED

EXECUTED THIS 29TH DAY OF DECEMBER, 1954

C. L. Gabbert

STATE OF KANSAS }
COUNTY OF SEDGWICK) SS

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC, WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 29th DAY OF December, 1954 PERSONALLY APPEARED C. L. Gabbert TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

MY COMMISSION EXPIRES 11-15-58

Sumner E. Hall
NOTARY PUBLIC

PLUGGING
FILE SEC 11 15 R20W
BOOK PAGE 17 LINE 1

REC
STATE
GOSPEY
Wichita

STATE OF KANSAS

INVOICE

December 23, 1954 19

To: Deep Rock Oil Corporation
Box 485
Hooker, Oklahoma

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

For: PLUGGING ASSESSMENT AS FOLLOWS:

Wann Well No. 1
NE NE NW Section 11-15-20W
Ellis County, Kansas
File No. 87-1

\$ 25.00

NOTE: We also need a written application, a well log and a well plugging record for the above described well in order to complete our file.

*Ad
Ch # 116954
1-13-55
JPK
C-141*

TO INSURE CORRECT APPLICATION KINDLY
RETURN PINK COPY WITH REMITTANCE



DEEP ROCK OIL CORPORATION, P. O. BOX 1051, TULSA 2, OKLAHOMA

DR-482-B

VOUCHER NO.	DESCRIPTION	GROSS AMOUNT	NET AMOUNT
12-869-30	12/23/54 STATEMENT		25.00