


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Ellis County, Sec. 35 Twp. 15S Rge. 19W (E) (W)  
Location as "NE/CNW&SW&" or footage from lines SE SE SW  
Lease Owner K & P Oil Company  
Lease Name Hansen Well No. A-1  
Office Address Box 682 Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) D&A  
Date well completed January 4, 19 62  
Application for plugging filed 19 62  
Application for plugging approved January 4, 19 62  
Plugging commenced January 4, 19 62  
Plugging completed January 4, 19 62  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3612 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

8 5/8" 1190' circulated with cement.  
Filled with heavy mud, set cementing plug at 540', displaced 20 sacks cement through drill pipe, heavy mud to 180', set plug and 20 sacks cement, heavy mud to 40', set plug, 1/2 sack hulls and 10 sacks cement to bottom of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 25 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Leben Drilling Company  
Address Box 486 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barber, ss.  
Leslie Kite (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) X Leslie Kite

SUBSCRIBED AND SWORN TO before me this 23 day of March, 1968  
Glenda D. Fisher (Address)  
My commission expires April 1, 1971 Notary Public.

DRILLER'S LOG

COMPANY: K. & P. Oil Company  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: Seelye-Hansen #1  
 LOCATION: C SE/4 SE/4 SW/4 Sec. 35-15S-19W  
 ELLIS COUNTY, KANSAS  
 COMMENCED: 12-21-61  
 COMPLETED: 1-4-62

0	610	Shale and Sand
610	770	Shale
770	945	Shale and Shells
945	1185	Shale
1185	1225	Anhydrite
1225	1860	Shale
1860	2135	Lime and Shale
2135	2190	Lime Fort Riley
2190	2295	Lime
2295	2505	Lime and Shale
2505	2950	Shale and Lime
2950	3045	Lime and Shale
3045	3105	Lime
3105	3165	Shale and Lime
3165	3170	Lime
3170	3250	Shale and Lime
3250	3295	Lime and Shale
3295	3596	Lime
3596	3600	Sand
3600	3612	Lime and Chert
	<u>3612</u>	<u>Rotary Total Depth - D. &amp; A.</u>

RECEIVED  
 STATE COMMISSION  
 JAN 10 1962  
 CONSERVATION DIVISION  
 Wichita Kansas

Set 8 5/8" Used Surface casing @ 1190' with 250 sacks Common, 2% C.C. with 250 sacks Sunset Cement.

I, Byron Johnson, do hereby certify that the above and foregoing is a true and correct copy of the log of the Seelye-Hansen #1, located C SE/4 SE/4 SW/4 of Section 35, Township 15 South, Range 19 West, Ellis County, Kansas, as reflected by the files of Leben Drilling, Inc.

*Byron Johnson*  
 \_\_\_\_\_  
 Byron Johnson

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON )

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 8th day of January, 1962.

*Betty S. Edman*  
 \_\_\_\_\_  
 Betty S. Edman, Notary Public

My Commission Expires:  
 November 8, 1964