

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas.

WELL PLUGGING RECORD

Ellis County, Sec. 10 Twp. 15S Rge. 19 (EX) (W)

Location as "NE/CNW/SW" or footage from lines NE NE SW

Lease Owner J. Stewart Bailey

Lease Name Gabel Well No. 1

Office Address 701 Union Nat'l Bank Bldg. Wichita, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9-1 19 53

Application for plugging filed 9-1 19 53

Application for plugging approved 9-1 19 53

Plugging commenced 9-1 11:00 A. M. 19 53

Plugging completed 9-1 1:00 P. M. 19 53

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes verbal

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3730 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Post Rock, Clay, Shale		0	185'	8 5/8	185'	None
Shale & Redbed		890	1249			
Anhydrite		1249	1295			
Lime, Shale, Shells		1295	3645			
Conglomerate (cherty)		3645	3706			
Arbuckle		3706	3730			
T. Depth		3730				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud
Set collar on top of surface pipe pumped 60 sacks of cement in surface pipe.
Under pressure

STATE CORPORATION COMMISSION
WICHITA, KANSAS
9-5-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strain Drilling Company

Address Box 188 Hays, Kansas.

STATE OF Kansas, COUNTY OF Ellis, ss.

T. C. Strain (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. C. Strain

Box 188 Hays, Kansas. (Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of 19 September, 19 53

Mildred Schneider

Notary Public.

My commission expires March 26, 1956

PLUGGING
FILE SEC 10 T. 15S R. 19W
BOOK PAGE 126 LINE 41

WELL LOG

CO. NY: Riggs, Bailey & Strain
 LEASE: Gabel # 1

NE NE SW Sec 10-
 Twp 15S, Rge 19W
 Ellis County, Kansas.

ELEVATION: 2040 R. B.

NOTE: All meas rotary Bushing

0	40 Post rock & Clay	3485	3535 Lime
40	90 Sand & Shale	3545	3595 Lime
90	185 Post Rock & Shale	3595	3645 Lime & Shale
185	200 Post Rock & Blue Shale	3645	3706 Cong. (Cherty)
200	410 Blue Shale & Shells	3706	3730 Arbuckle
410	470 Sand	3730	(Total Depth)
470	660 Shale & Shells		
660	890 Sand		
890	980 Shale & Redbed	COMMENCED: 8-22-53	
980	1080 Shale & Redbed	COMPLETED: 9-1-53	
1080	1160 Redbed		
1160	1249 Redbed & Shale	CASING RECORD:	
1249	1295 Anhydrite		
1295	1440 Shale & Shells		8 5/8 Surface Casing set at 185' w/115
1440	1605 Shale & Lime		sacks of cement by Sun Cementing Co.
1605	1770 Shale & Lime		
1770	1870 Shale & Salt		
1870	1960 Lime & Shale	D.S.T. by Halliburton	
1960	2150 Lime & Shale		
2150	2230 Shale & Lime		3353-3420 Tool open @ 10:19 good blow
2230	2265 Lime & Shale		for 1 hour. Recovered 5' of Oil and
2265	2270 Lime & Shale		230' of salt water. 15 min B.H.P. 1125#
2270	2350 Lime (Hard)		Schlumberger Logs Run
2350	2450 Lime		
2450	2480 Shale & Lime		Geologist: K. T. Woodman
2480	2520 Lime & Shale		
2520	2553 Lime		
2553	2720 Shale & Lime		
2720	2880 Shale & Lime		
2880	2910 Lime & Shale		
2910	2980 Shale & Lime		
2980	3105 Lime & Shale		
3105	3205 Shale & Lime		
3205	3285 Shale & Lime		
3285	3335 Lime		
3335	3390 Lime		
3390	3420 Lime		
3420	3435 Lime		
3435	3485 Lime		

TOPS: Geological

Anhydrite	1249 (+791)	Lansing K. C.	3331 (-1291)
Heebner	3287 (-1247)	Conglomerate	3645 (-1605)
Tronto	3305 (-1265)	Arbuckle	3706 (-1666)
		T. Depth 3730	(-1690)

STATE OF KANSAS) SS
 COUNTY OF ELLIS)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Gabel # 1, located NE NE SW, Sec 10, Twp 15S, Rge 19W, Rooks County, Kansas.

CONTRACTOR: Strain Drilling Company

BY: T. C. Strain
 T. C. Strain

Subscribed and sworn to before me this 3rd day of August 1953.
 My commission expires March 26, 1956

PLUGGING
 FILE SEC 10 T. 15 R. 19W
 BOOK PAGE 41 LINE 41

Mildred Schneider
 Notary Public