


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Ellis \_\_\_\_\_ County. Sec. 1 Twp. 15S Rge. 19W (E) \_\_\_\_\_ (W) \_\_\_\_\_



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines SE SE NW  
Lease Owner Alpine Oil & Royalty Co., Inc.  
Lease Name Anton Pfannenstiel Well No. 1  
Office Address 800 Bitting Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry (lost hole)  
Date well completed September 24, 1965 19\_\_\_\_  
Application for plugging filed September 24, 1965 (phone) 19\_\_\_\_  
Application for plugging approved September 24, 1965 (phone) 19\_\_\_\_  
Plugging commenced September 24, 1965 19\_\_\_\_  
Plugging completed September 24, 1965 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3305 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	207'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Dropped drill pipe, pipe stuck, left 1241 feet of 4 1/2 inch pipe in hole.

Set plug at 540 feet with 20 sacks cement; 2nd plug at 180 feet with 20 sacks cement; top plug at 35 feet with 1/4th sack hulls below plug and 10 sacks cement to bottom of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 13 1965

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Globe Oil Well Cementing Company  
Address Great Bend, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Dwight J. Wilson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dwight J. Wilson  
800 Bitting Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of October, 19 65

My commission expires August 10, 1969  
Virginia Mundell Notary Public.

GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

PFANNENSTIEL #1  
SE SE NW SECTION 1-15S-19W  
ELLIS COUNTY, KANSAS

COMMENCED: SEPTEMBER 16, 1965  
COMPLETED: SEPTEMBER 24, 1965

OPERATOR - ALPINE OIL & ROYALTY CO., INC.

DEPTH		FORMATION	REMARKS
FROM	To		
0	40	SURFACE CLAY AND SHELLS	
40	207	SHALE AND SHELLS	RAN 207' OF 8-5/8" CASING, SET w/165 SACKS CEMENT.
207	295	RED BED	
295	700	RED BED AND SHALE	
700	975	SAND	
975	1155	SHALE	
1155	1304	RED BED AND SHALE	
1304	1350	ANHYDRITE	
1350	1480	SHALE AND SHELLS	
1480	2320	SHALE AND LIME	
2320	2525	LIME	
2525	3230	SHALE AND LIME	
3230	3305	LIME	
3305	TD		DROPPED DRILL PIPE, PIPE STUCK, LEFT 1241' OF 4 1/2" PIPE IN HOLE, HOLE ABANDONED.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 13 1965  
CONSERVATION DIVISION  
Wichita, Kansas

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE SE SE NW SECTION 1-15S-19W, ELLIS COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall  
E. E. HALL

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 6TH DAY OF OCTOBER, 1965, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton  
BARBARA J. LAYTON, NOTARY PUBLIC

MY COMMISSION EXPIRES FEBRUARY 1, 1968.