

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give Full Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Ellis County, Sec. 33 Twp. 15 Rge. 18 (E) W(W)

Location as "NE/CNW/SW" or footage from lines SE SE NE

Lease Owner C-G Drilling Co.

Lease Name Werth Well No. 1

Office Address 107 Rule Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10-4 1954

Application for plugging filed 10-4 1954

Application for plugging approved 10-4 1954

Plugging commenced 10-4 1954

Plugging completed 10-4 1954

Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production -- 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation -- Depth to top -- Bottom -- Total Depth of Well 3546 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1123.15	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Welded collar on top of surface casing.
Put plug in. Pumped 80 sacks cement in surface pipe through swedge. Hole filled to top.

10-9-54
IVED
COMMISSION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G Drilling Co.

Address 107 Rule Building, Wichita, Kansas,

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Vicky Jacobs

(employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Vicky Jacobs Office Manger
107 Rule Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of October, 1954

Barbara Donaldson Notary Public.

My commission expires June 17, 1957

PLUGGING
FILE SEC 33 T 15 R 18 W
BOOK PAGE 69 LINE 13

CONTRACTOR'S WELL LOG

OPERATOR C-G Drilling Co. FARM NAME Werth #1
 LOCATION SE SE NE, Sec. 33-15-18W
 POOL NAME _____ COUNTY Ellis STATE Kansas
 COMMENCEMENT DATE September 23, 1954 COMPLETION DATE October 4, 1954

LOG OF WELL

Elevation: 1959 R.B.
 All measurements from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	450	Shale-Shells-Sand		
450	530	Shale-Shells		
530	760	Sand		
760	885	Shale-Shells		
885	1118	Red-Bed-Shale		
1118	1155	Anhydrite		
1155	1415	Shale-Sandy Shale		
1415	1885	Shale-Shells	0° - 1500'	
1885	2135	Shale-Shells	0° - 2000'	
2135	2185	Lime-Shale		
2185	2307	Lime-Shale-Sand		
2307	2510	Lime-Shale	0° - 2500'	
2510	2655	Lime-Shale		
2655	2800	Lime-Shale		
2800	2950	Lime-Shale		
2950	3070	Shale-Lime	0° - 3000'	
3070	3134	Lime-Shale		
3134	3180	Lime-Shale		
3180	3250	Lime-Shale		
3250	3319	Lime-Shale		
3319	3359	Lime-Shale		
3359	3400	Lime-Shale		
3400	3445	Lime		
3445	3486	Lime-Shale		
3486	3532	Lime-Shale	0° - 3500'	
3532	3536	Lime-Shale		DST: 3528-32
3536	3546	Lime		DST: 3528-36
3546	3546	Lime		DST: 3528-46

CASING LEFT IN HOLE AFTER COMPLETION

Ran 1123.15 (38 jts) of 8-5/8" Surface Casing.

STATE OF KANSAS, COUNTY OF SEDGWICK) SS.

The undersigned certifies that to the best of her knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By Wicky Jacobs Office Manager

Subscribed and sworn to before me this 7th day of October, 1954.

My commission expires: June 17, 1957

Barbara Donaldson
 Notary Public

PLUGGING
 WELLS SEC 33-15-18W
 PAGE 69 LINE 13