


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Ellis County. Sec. 20 Twp. 15 Rge. 18W (X) (W)
Location as "NE/CNW/SW" or footage from lines SE 1/4 SE 1/4 SE 1/4
Lease Owner Arnell Company
Lease Name Wiesner "A" Well No. 1
Office Address 533 Petroleum Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed 10-28-57 19
Application for plugging filed 10-28-57 19
Application for plugging approved 10-28-57 19
Plugging commenced 10-28-57 19
Plugging completed 10-28-57 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13 3/8	104'	
				8 5/8	1112'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st Plug @ 500' w/30 sacks cement
2nd Plug @ 250' w/30 sacks cement
Top Plug @ 40' w/10 sacks cement & 1 sx CaCl.

11-14-57

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Leben Drilling, Inc.
Address 905 Central Bldg., Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick SS.
I, Frank Hamlin (employee of Leben Drilling, Inc. or Contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Hamlin
905 Central Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of November, 19 57

My commission expires June 17, 1961
Ruth N. Benjamin Notary Public.

NOV 14 1957
CONSERVATION DIVISION
Wichita, Kansas
REC 20 T. 15 R. 18W
BOOK PAGE 58 LINE 17

CONTRACTOR'S WELL LOG

COMPANY: ARTNELL COMPANY
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: WIESNER "A" #1
 LOCATION: SE SE SE Sec. 20-15S-18W
 Ellis County, Kansas
 COMMENCED: 10-14-57
 COMPLETED: 10-28-57

0	104	Shale & Sand
104	315	Shale & Shells
315	1095	Shale & Sand
1095	1105	Chalk
1105	1113	Anhydrite
1113	1155	Lime
1155	1895	Shale & Shells
1895	2100	Shale & Lime
2100	2265	Lime
2265	3065	Lime & Shale
3065	3295	Lime
3295	3550	Lime
3550	3610	Lime
	<u>3610</u>	<u>Rotary Total Depth - D & A</u>

Set 104' of 13-3/8", 48# surface casing with 100 sacks cement & 2 sacks CaCl.
 Set 1112' of 8-5/8", 24# surface casing with 575 sacks cement & 2 sacks CaCl.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Wiesner "A" #1, located SE $\frac{1}{4}$ SE $\frac{1}{4}$ SE $\frac{1}{4}$ of Section 20, Township 15 South, Range 18 West, Ellis County, Kansas, as reflected by the files of Leben Drilling, Inc.

LEBEN DRILLING, INC.

By: Frank Hamlin
 Frank Hamlin

STATE OF KANSAS)
 COUNTY OF SEDGWICK) ss

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 6th day of November, 1957.

Ruth N. Benjamin
 Ruth N. Benjamin - Notary Public

My Commission Expires:
 June 17, 1961

NOV 11 1957
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 20 T 15 R 18W
 BOOK PAGE 58 LINE 17