

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Petroleum, Inc., c/o Pipe Pullers, Inc.

Complete Address: Box 486, Ellinwood, Kansas

Lease Name Hufford (Hazel South Flood Unit #2-1) Well No. # A-7

Location SW NW-NW Sec. 28 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3755'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Pipe Pullers, Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 11:30AM Day 23rd Month Feb. Year 1966

The Above well was plugged as follows:

215' of 8 5/8" surface pipe, cemented with 200 sacks. 3754' of 5 1/2" long string, cemented with 75 sacks. Plug back TD 3580'. Top perferation 3398'. Bottom plug was pushed to 3380', 50' of sand, and cemented with 5 sacks. 3128' of 5 1/2" long string was recovered from the hole. Fluid was up in the hole. Bridge plug was pushed in fluid to 200', rock bridge from 200' to 190'. 8 sacks of cement was mixed in a barrel, and put on plug at 190', through the dump bailer, and let set over-night. Next morning hole was bailed dry, and 17 sacks of cement was added to the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

STATE CORPORATION COMMISSION

Signed: Archie Elving  
Well Plugging Supervisor

DATE

2/24/66

FEB 24 1966

INV. NO.

2999-W

CONSERVATION DIVISION  
Wichita, Kansas