

R KANSAS STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED STATE CORPORATION COMMISSION

JUN 14 1963

J. P. Roberts Assitant Director 500 Insurance Building 212 North Market Wichita 2, Kansas

CONSERVATION DIV. Wichita, Kansas

Operator's Full Name Independent Lease Management Co.

Complete Address: 302 Union Center, Wichita, Kansas.

Lease Name Goering Well No. B-3

Location SW SW NW Sec. 35 Twp. 21 Rge. 3 X(E) (W)

County McPherson Total Depth 3595'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 305, Chase, Kansas License No. 436

Operation Completed: Hour 3:PM Day 5 Month 6 Year 63

The Above well was plugged as follows:

Filled hole w/ sand from T.D. 3595' back to 3530' ran 5 sax cement w/ dump bailer. Shot off and pulled 5 1/2" casing. Filled hole w/ mud from 3505' back to 200' set a 10' rock bridge ran 20 sax cement from 190' back to 125'. Filled hole w/ mud from Back to 30' set a 5' rock bridge and ran 8 sax cement from 25' back to zero 3' below ground level. 8 5/8" surface pipe 3' below ground level.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/14/63

INV. NO. 7261-W

Signed: [Signature] Well Plugging Supervisor