

15.113.02156.0000

Form CP-3
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 1 1 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Independent Lease Management Company

Complete Address: 300 Wichita Plaza. Wichita, Kansas 67202

Lease Name Fehring Krehbiel Well No. C-3

Location C EL NW SE Sec. 35 Twp. 21 Rge. 3 (E) / (W)

County McPherson Total Depth 3595'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company Inc.

Address: Chase, Kansas License No. 624

Operation Completed: Hour 5 PM Day 10 Month 10 Year 68

The Above well was plugged as follows:

8 5/8"-210'-Circulated w/cement. 5 1/2"-3595'-Cemented. Top Perf. 3539'.

Plug back bottom w/15 Sax.cement top cement at 3474'. Halliburton cementing Co.

Mud 3475' to 240'. Bridge 240' to 220'. 25 Sax.cement 221' to 150'.

Mud 150' to 40'. Bridge 40' to 30'. 16 Sax.cement. 30' to 0.

Pulled 2983'-5 1/2"-pipe.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 10/11/68
INV. NO. 8610-u