

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: McPherson

Location CN2- SE- SW Sec. 35 Twp. 21 Rge. 3 (E) (W)

Name of Field: Hollow Total Depth: 3557'

I have this date completed supervision of plugging of:

Lease Name: Krehbiel Well No. 2

Operator's Full Name: E K. Carey Drilling Co.

Complete Address: 200 E. Ave, F. McPherson Kansas.

Plugging Contractor: Bert Self Casing Pulling Co.

Address: R.R. 4 Hutchinson Kansas License No. 48

Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other Well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes No X

If yes how long? _____ Reason: _____

Operation Completed: Hour 3:PM Day 16 Month 2 Year 61

The above well was plugged as follows:

Filled hole w/ sand from T.D. 3557' back to 3503' ran 5 sax cement w/ dump bailer.
Shot off and pulled 5 1/2" casing. Filled hole w/ mud from 3440' back to 240' set 10'
rock bridge and 20 sax cement. Filled hole w/ mud from 180' back to 35' set 10'
rock bridge and 8 sax cement. 8 5/8" surface pipe 3' below ground level

RECEIVED
STATE CORPORATION COMMISSION
FEB 28 1961
CONSERVATION DIVISION
WICHITA, KANSAS

Reviewed: Graham

Signed: Cecil M. Jones
Conservation Division Agent

Remarks:

INVOICED
DATE 3-6-61
INV. NO. 3100-E