

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -113 -20290.0000 (of this well)

Operator's Full Name Kelso Casing Pulling
Complete Address Box 176, Chase, Kansas 67524
Lease Name Stucky "B" Well No. 1
Location W/2 NW NW Sec. 3 Twp. 21 Rge. 3 (E) (W) X
County McPherson Total Depth 3466'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Operator
Address License No. 683

Operation Completed: Hour 3:30 PM Day 15 Month July Year 1980

The above well was plugged as follows: 8 3/8" - 225' - 200 sacks 4 1/2" - 3466' - 250 sacks.
Hole filled with sand to 3400' and cemented with 3 sacks
Hole bailed to 260'. Rock bridge set from 260' - 245' and
hole cemented to base of cellar with 4 1/2 yards
ready-mix.
2231' of 4 1/2" casing recovered.

RECEIVED
STATE CORPORATION COMMISSION
JUL 22 1980

I hereby certify that the above well was plugged as herein stated.

CONSERVATION DIVISION
Wichita, Kansas
Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 8-28-80
INV. NO. 2981-w