


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Mc Pherson County, Sec. 17 Twp. 21 Rge. 1 W (E) (W)
Location as "NE/CNW/SW" or footage from lines SW/NE/SE
Lease Owner Alfred Koehn
Lease Name Goering Well No. 7
Office Address Galva, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed March 5 19 37
Application for plugging filed June 19 62
Application for plugging approved June 19 62
Plugging commenced June 19 19 62
Plugging completed June 28- 19 62
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3344' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"		3,040'
				7"		2,395'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole with rock. Rock from 3,014' to 3,005'. Dumped 5 sx of cement. Plugged hole to 3,005' to 2,930' with rock. Plugged hole from 160' to 150'. Made 10' od rock bridge. Dumped 3 1/2 yds of Ready-Mix Cement, filling to the bottom of the celler.

RECEIVED
STATE CORPORATION COMMISSION
JUL 2 1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address P.O. Box 983 Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb
2809 Kings Drive, Hutchinson, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28 th day of June, 19 62


My commission expires January 5, 1966
[Signature] Notary Public.

THE DICKEY OIL CO.
 Goering No. 7.

SEC. 17 T. 21 R. 1W
 SW NE SE

Total Depth. 3344
 Comm. 2-5-37 Comp. 3-5-37
 Shot or Treated.
 Contractor.
 Issued. 4-3-37

County. McPherson



CASING:
 10" 156'
 7" 3319' *15' O. D.*
 4 1/2" 3014' *<Liner>*

Elevation. 1488
 - 1831
 Production. Pot. 1360 B.

Figures Indicate Bottom of Formations.

surface	156
shale & shells	371
brkn lime	900
shale & shells	1664
brkn lime	1816
lime	1842
brkn lime	1954
lime	2093
brkn lime	2353
lime	2640
brkn lime	2811
shale	2915
ohat	3040
lime	3110
shale	3319
lime	3344
Total Depth, -	-

- Top of Hunton 3319 -

PERFORATING CHAT FOR GAS

Lane Wells Company
 January 19 1939.

Gun Perforating 84 holes in 7" O. D. Casing.

Between 2945 - 2970	395.20
72 miles @ 15¢.	<u>10.80</u>
	406.00

First Shot	2945
First Show Gas	2960
Increase	2966 -2970
24 shots at	2966 -2970

Gas Test - 800# Pressure

5,200 M. Cu. Ft. immediately after shooting.
 Seemed to increase after packer was set. Lane Wells
 Packer collapsed; made two attempts to set it then
 removed it and put in an Oil Well 5-3/16" - 7" O. D.
 packer which we had in warehouse.

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 9 1962
 CONSERVATION DIVISION
 Wichita, Kansas