

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to...
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Mc Pherson County, Sec. 17 Twp. 27 Rge. I W (E) (W)
Location as "NE/CNW/SW" or footage from lines SW/4 NW/4 NE/4
Lease Owner George Hess
Lease Name ~~George Hess~~ Goering Well No. I
Office Address 505 North Charles, Mc Pherson, Kansas 67460
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 9-9 1968
Application for plugging filed 5-5 1971
Application for plugging approved 5-6 1971
Plugging commenced 5-17 1971
Plugging completed 5-27 1971
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3428 1/2 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				<u>4 1/2"</u>		<u>2,700'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3428 to 3350'. Dumped 4 sx of cement. Mudded hole to 150'. Made 10' of rock bridge. Dumped 25 sx of cement. Mudded hole to 40'. Made 10' of rock bridge. Dumped 10 sx of cement, filling to the bottom of the cellar.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Reno, ss.

Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

2809 King St. Hutchinson, Kansas 67501
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of May, 1971

My commission expires: January 5, 1974

[Signature]
Notary Public.



Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON • KANSAS
67460

Sept. 10, 1968

RECEIVED
STATE CORPORATION COMMISSION

MAY 7 1971
CONSERVATION DIVISION
Wichita, Kansas

COMPANY: GEORGE R. HESS & SONS
CONTRACTOR: BLACKSTONE DRILLING, INC.
FARM: HERB J. Goering # 1
LOCATION: SW/4 NW/4 NE/4, Sec. 17-21-1W,
McPherson County, Kansas
COMMENCED: Sept. 3, 1968
COMPLETED: Sept. 9, 1968
ELEVATION: 1500 K.B.

0	to	35	Shale
35	to	40	Sand
40	to	135	Shale
135	to	625	Shale & Lime
625	to	950	Lime
950	to	2280	Lime & Shale
2280	to	2319	Lime
2319	to	2770	Kansas City
2770	to	2949	Lime & Shale
2949	to	3234	Mississippi
3234	to	3350	Shale & Lime
3350	to	3428 1/2	Lime
		3428 1/2	T. D.

Cut 12 1/4 in. hole to 135 ft. and run 137 ft. of 8 5/8 in. surface pipe, cemented with 95 sacks on bottom at 135 ft. Plug down at 3:00 P.M., September 3, 1968. Cut 7 7/8 in. hole to 3428 1/2 ft. and run 3858 ft. of 4 1/2 in. casing and cemented with 35 sacks at 3355 ft. Plug down at 1:15 P.M., September 9, 1968. 2 sacks in rathole.

TOPS: Blue Shale - 50' Kansas City - 2319' Mississippi - 2949'

Measurements taken from K.B.

CERTIFICATE


I, H. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Herb J. Krehbiel #1, located on the SW/4 NW/4 NE/4 of Sec. 17-21-1W, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc.


H. J. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 10th day of September, 1968.


Ruth McVay - Notary Public

My Commission Expires: Dec. 18, 1969.



Dear Sir:

Mr. Geo Hess said the
correct name on this lease
should be Herb Spring #1.
I have perhaps copied
down Herb Furbill. Would
you please be so kind as to
correct it, if I've put the
wrong name - Thank you - Mrs. Lent