

15.145.00794.0000

6-19-98

STATE OF KANSAS
STATE CORPORATION COMMISSION
30 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 1953

LEASE NAME Phinney

WELL NUMBERS C#2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

3630 Ft. from S Section Line

1980

990 Ft. from E Section Line

SEC. 34 TWP. 21S RGE. 16W (E) or (W)

COUNTY Pawnee

Date Well Completed _____

Plugging Commenced 06-05-98

Plugging Completed 06-05-98

LEASE OPERATOR Pintail Petroleum Ltd.

ADDRESS 225 N. Market #300 Wichita, KS 67202

PHONE (316) 263-2243 OPERATORS LICENSE NO. 5086

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 06-05-98 (date)

by Richard Lacey (XCC District Agent's Name).

Is ACC-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom Openhole T.D. 3869'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	-0-	1023'	8 5/8"	1023'	-0-
	Production	-0-	3866'	5 1/2"	3866'	1999.30

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Allied shot off at 2000', pulled to 1000' & spot 10 sacks gel and 50 sacks cement 60/40, 6% gel. Pulled to 500' & spot 40 sacks cement, pulled to 40' and circulated cement to surface with 10 sacks and 5 sacks cement in cellar. Hole stayed full. Job started 11:00 a.m. and completed at 1:00 p.m.

Name of Plugging Contractor D.S. & W. Well Servicing, Inc. License No. 6901

Address P.O. Box 231 Claflin, KS 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pintail Petroleum Ltd.

STATE OF Kansas COUNTY OF Barton, ss.

Joseph F. Strube (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Joseph F. Strube

(Address) P.O. Box 231 Claflin, KS 67525

SUBSCRIBED AND SWORN TO before me this 17th day of June, 19 98

Brenda Urban

My Commission Expires: Nov 14, 2001

Notary Public
BRENDA URBAN
Notary Public - State of Kansas
My Appt. Expires Nov 14, 2001