

APR 2 - 1974


CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Commission

P. O. Box 17027  
Wichita, Kansas 67217  
NORTH



Locate well correctly on above  
Section Plat

Pawnee County, Sec. 34 Twp. 21 Rge. 16 (E) (W) X  
 Location as "NE/CNW/SESW4" or footage from lines SE SE NW  
 Lease Owner: A. L. Abercrombie, Inc.  
 Lease Name: Fairbanks Well No. #1  
 Office Address: 801 Union Center Wichita, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
 Date well completed \_\_\_\_\_ 19\_\_\_\_  
 Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
 Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
 Plugging commenced \_\_\_\_\_ 3-15-74 \_\_\_\_\_ 19\_\_\_\_  
 Plugging completed \_\_\_\_\_ 3-30-74 \_\_\_\_\_ 19\_\_\_\_  
 Reason for abandonment of well or producing formation \_\_\_\_\_  
 If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well: Leo Massey  
 Producing formation: \_\_\_\_\_ Depth to top: \_\_\_\_\_ Bottom: \_\_\_\_\_ Total Depth of Well: 3941' Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3939'	2876.38'
				8 5/8"	943'	


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Made bottom hole plug back with sand to 3500'. Mixed and dumped 4 sacks cement thru dump bailer.  
 Mudded hole to 325' - set 25' rock bridge. Filled hole with 4 yards ready mix to base of cellar.

Name of Plugging Contractor: Southwest Casing Pulling Co. (If additional description is necessary, use BACK of this sheet)  
 Address: Box 364 Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton  
 Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed, and that the same are true and correct. So help me God.



(Signature) \_\_\_\_\_  
 Box 364 Great Bend, Kansas (Address)  
 \_\_\_\_\_ 19 74  
 Sidney D. Miller  
 Notary Public.

Signed and sworn to before me this 1 day of April  
 My commission expires 29 October 1976

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 17 1973  
CONSERVATION DIVISION  
Wichita, Kansas

CONTRACTOR'S WELL LOG

COMPANY: Musgrove Petroleum Corporation  
 CONTRACTOR: Musgrove Petroleum Corporation  
 NAME: Fairbanks #1  
 LOCATION: SE SE NW Section 24-21-27 16  
 Pawnee County, Kansas  
 COMMENCED: September 23, 1952  
 COMPLETED: October 10, 1952

0	110	Surface Sand & Clay
110	315	Sand & Clay
315	425	Red Red & Shale
425	520	Sand
520	545	Red Bed
545	690	Red Bed, Sand & Shale
690	875	Shale & Shells
875	943	Shale & Lime
943	980	Shale & Shells
980	1015	Anhydrite
1015	1750	Shale & Shells
1750	1775	Shale
1775	3038	Lime & Shale
3038	3941	Lime
	3941	Rotary Total Depth

Set 950.50' of 8-5/8" surface casing, cemented with 500 sacks.  
 Set 3965.93' of 5-1/2", cemented with 150 sacks.

STATE OF KANSAS }  
 COUNTY OF SEDGWICK } SS.

I, GORDON L. RICHMOND, do hereby certify that the above and foregoing is a true and correct copy of the log of Fairbanks #1, Section 24-21-27, Pawnee County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

By: *Gordon L. Richmond*  
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, within and for Sedgewick County, Kansas, this 15th day of October, 1952.

*Gordon L. Richmond*  
 Notary Public

My Commission Expires: September 24, 1956.