

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.--82-3-117

API NUMBER 15.145.00784.0000

LEASE NAME Dipman

WELL NUMBER #1

2310 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 34 TWP. 21 RGE. 16 (E) or (W)

COUNTY Pawnee

Date Well Completed 11-27-52

Plugging Commenced 3-15-89

Plugging Completed 3-28-89

LEASE OPERATOR Hilliker Production

ADDRESS 3315-16th, Great Bend, Ks. 67530

PHONE# (316)-793-7519 OPERATORS LICENSE NO. 7230

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? March 28, 1989

Which agent did you notify? Duane Rankin

Is ACO-1 filed? If not, is well log attached? With application

Producing Formation Depth to Top Bottom T.D. 3857'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	900'	None
				5-1/2"	3854'	2,437.70'

RECEIVED
 STATE CORPORATION COMMISSION

APR 5 1989
 CONSERVATION DIVISION
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 3800' and 5 sacks cement. Shot casing at 3000', 2800', 2600', 2400'. Pulled 74 joints of 5-1/2" casing. Howco plugged well with 4 sacks hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 1 sacks hulls and 120 sacks 60/40 pozmix cement with 6% gel. Maximum pressure was 500 psi and shutin 300 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
 (Address) Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 31st day of March, 1989

STATE NOTARY PUBLIC
 IONA M. LEATHERMAN
 Barton County, Kansas
 My Appt. Exp. 9-26-91

Iona M. Leatherman
 Notary Public

My Commission Expires: