

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15.145.00797.0000

LEASE NAME Weiman

WELL NUMBER #2

4290 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 34 TWP. 21 RGE. 16 (E) or (W)

COUNTY Pawnee

Date Well Completed 6-19-53

Plugging Commenced 3-22-89

Plugging Completed 3-28-89

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Hilliker Production

ADDRESS 3315-16th, Great Bend, Ks. 67530

PHONE 316-793-7519 OPERATORS LICENSE NO. 7230

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? March 22, 1989

Which agent did you notify? Richard Lacey and Duane Rankin

Is ACO-1 filed?                      If not, is well log attached? With application

Producing Formation                                      Depth to Top                      Bottom                      T.D. 3865'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	975'	None
				5-1/2"	3853'	2,534.08'

RECEIVED  
 STATE CORPORATION COMMISSION

APR 5 1989

CONSERVATION DIVISION  
 WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 3790' and 5 sacks cement. Shot casing at 3100', 2800' and 2500'. Pulled 61 joints of 5-1/2" Hydrid CS casing. Howco plugged well with 400# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 1 sack hulls, released plug and pumped 120 sacks 60/40 pozmix cement with 6% gel. Maximum pressure was 850 psi and shutin 750 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.


James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold  
 James W. Rockhold  
 (Address) Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 31st day of March, 1989

Iona M. Leatherman  
 Notary Public

My Commission Expires



## WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15145.00797.0000

Company. MUSGROVE PETROLEUM CORPORATION

SEC. 34 T. 21 R. 16W  
SE NE NWFarm. Weiman *Weiman* No. 2

Total Depth. 3854

Comm. 5-16-53

Comp. 5-31-53


County Pawnee

KANSAS

Shot or Traced:

Contractor. Musgrove Petroleum Corporation

Issued. 7-25-53



## CASING:

8 5/8 set at 975' w/ 450 sx cement

5 1/2 set at 3853' w/ 150 sx cement

Elevation. 1993

Production. DD 3000 BO, no W

Figures indicate Bottom of Formations.

sand & gravel	155
shale & shells	275
shale	370
shale; shells & red bed	750
shale, red bed & pyrite	875
shale & pyrite	975
shale	987
anhydrite	1010
shale & shells	1790
lime & shale	3190
lime	3851
Arbuckle	3854
Total Depth	

## SCOUT TOPS:

Anhydrite	970
Heebner	3392
Brown lime	3490
Lansing	3499
Base KC	3722
Conglomerate	3774
Arbuckle	3852

RECEIVED  
STATE CORPORATION COMMISSION

MAR 27 1953

CONSERVATION DIVISION  
Wichita, Kansas