


15.145.20803.0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Pawnee County, Sec. 34 Twp. 21 Rge. 16 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
NE SE NW  
Lease Owner Stalcup Oil Co.  
Lease Name Carr Well No. 1  
Office Address 3511 - 23rd, Great Bend, Ks.  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plot

Dry Hole  
Date Well completed Feb. 4 1981  
Application for plugging filed Feb. 4 1981  
Application for plugging approved Feb. 4 1981  
Plugging commenced Feb. 4 1981  
Plugging completed Feb. 4 1981  
Reason for abandonment of well or producing formation

Dry Hole  
If a producing well is abandoned, date of last production 19.

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt  
Producing formation Depth to top Bottom Total Depth of Well 3854  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	976'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

First plug @ 900' w/65 sacks cement  
270' w/30 sacks solid bridge plug &  
40' w/10 sacks  
5 sacks in rat hole  
50/50 Pozmix 4% Gel.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Mustang Drilling & Exploration, Inc.

STATE OF Kansas COUNTY OF Barton, ss.  
Milford Martin (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature)

Box 1425, Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of February, 19 81



Beverly Shewbart  
Notary Public.

My commission expires April 14, 1982

STATE CORPORATION COMMISSION  
FEB - 9 1981 2-9-81  
CONSERVATION DIVISION  
Wichita, Kansas

DRILLERS' WELL LOG

DATE COMMENCED: January 29, 1981  
DATE COMPLETED: February 4, 1981

Stalcup Oil Co.  
"CARR # 1"  
NE SE NW  
Sec 34-T21-R16W  
Pawnee County, Kansas

ELEVATION: 1989 K.B.

0 - 420' Sand, Blue Shale  
420 - 505' Sand  
505 - 600' Red Bed  
600 - 970' Red Bed, Shale  
970 - 980' Anhydrite  
980 - 1535' Shale  
1535 - 3546' Shale, Lime  
3546 - 3736' Lime, Shale  
3736' - 3854' Lime  
3854' RTD

API # 15-145-20,803

No Tops

SURFACE PIPE:  
Set used 8 5/8", 24# pipe  
@ 976' w/150' sacks Common,  
4% Gel, 3% cc. followed by  
225 sacks Common, 2% Gel, 3% cc.

A F F I D A V I T

STATE OF KANSAS )  
COUNTY OF BARTON ) ss.

I, Milford Martin, of Mustang Drilling & Exploratoin, Inc. do state  
that the above is true and correct to the best of my knowledge.

*Milford Martin*  
\_\_\_\_\_  
Milford Martin

Subscribed and and sworn to before me this 5th day of February, 1981.

*Beverly Sheward*  
\_\_\_\_\_  
Notary Public

NOTARY PUBLIC  
BEVERLY SHEWDART  
Barton County, Kansas  
My Appt. Exp. \_\_\_\_\_

My Commission Expires: April 14, 1982

STATE OF KANSAS  
FEB - 9 1981  
COMMISSION DIVISION  
Topeka, Kansas