


STATE OF KANSAS
STATE CORPORATION COMMISSION

Take All Information Completely
State Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Pawnee County, Sec. 34, T. 21, R. 16 (E) (W) X
Location as "NE/CNW/SW" or footage from lines: NE SE NW
Lease Owner: A. L. Abercrombie, Inc.
Lease Name: Fairbanks Well No. #4
Office Address: 801 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed: 19____
Application for plugging filed: 19____
Application for plugging approved: 19____
Plugging commenced: 3-5-74 19____
Plugging completed: 3-14-74 19____
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production: 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well: Leo Massey
Producing formation: _____ Depth to top: _____ Bottom: _____ Total Depth of Well: 3845' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"	3844'	1445.21'
				10 3/4"	1000'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Made bottom hole plug back with sand to 3825'. Mixed and ran 5 sacks cement thru dump bailer.

Mudded hole to 460' - set 60' rock bridge. Filled hole with 7 yards ready mix concrete to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

3-18-74 MAR 18 1974

CONSERVATION DIVISION
Wichita, Kansas


Name of Plugging Contractor: Southwest Casing Pulling Co.
Address: Box 364 Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton ss.

Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.
Box 364 Great Bend, Kansas
(Address)

Subscribed and sworn to before me this 15 day of March 1974



Sydney D. Miller Notary Public.

CONTRACTOR'S WELL LOG

COMPANY: Musgrove Petroleum Corporation
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: FAIRBANKS #4
 LOCATION: NE SE NW Sec. 34-21-16
 Pawnee County, Kansas.
 COMMENCED: July 10, 1953
 COMPLETED: July 21, 1953

0	135	Sand
135	420	Shale & shells
420	540	Sand
540	655	Sand & shale
655	700	Shale & red bed
700	900	Bl. shale
900	915	Red bed & anhydrite
915	998	Shale
998	1000	Anhydrite
1000	1140	Shale
1140	1655	Shale & shells
1655	1745	Salt & shale
1745	1895	Shale & lime shells
1895	2070	Shells & shale
2070	2215	Lime
2215	3220	Lime & shale
3220	3330	Lime
3330	3480	Lime & shale
3480	3841	Lime
3841	3845	Arbuckle
	3845	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 17 1973
 CONSERVATION DIVISION
 Wichita, Kansas

Set 10-3/4" surface casing at 1000' with 450 sacks of cement.

Set 7" pipe at 3844' with 150 sacks cement.

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the Fairbanks #4, NE SE NW, Section 34-21-16, Pawnee County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

BY *Gordon L. Koelling*
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 30th day of July, 1953.

Notary Public

My commission expires September 24, 1956.