


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County, Sec. 34 Twp. 21 Rge. 16 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

SW SW NE
Lease Owner A. L. Abercrombie, Inc.
Lease Name Phinney #1 Well No. _____
Office Address Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 11/13/78 _____ 19____
Plugging completed 12/1/78 _____ 19____
Reason for abandonment of well or producing formation _____

depleted.
If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3853.5
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	948	none
				5 1/2"	3848.5	2033

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 3825', ran 4 sacks cement. Shot pipe at 2713', 2608', 2500', 2402', 2320', 2226', 2128', 2030', pulled 62 joints. Pumped 20 sacks gel, plug and 110 sacks 50-50 pos with 6% gel.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

12-8-78 DEC - 8 1978

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS


STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of Dec., 19 78

Margaret Melcher
Notary Public.

My commission expires _____



CONTRACTORS WELL LOG

COMPANY:	Musgrove Petroleum Corporation
CONTRACTOR:	Musgrove Petroleum Corporation
FARM:	Whinney #1
LOCATION:	SW SW NE Section 34-21E-16N Pawnee County, Kansas
COMMENCED:	July 26, 1952
COMPLETED:	August 4, 1952

0	85	Sand, gravel, sandy shale
85	150	Shale
150	200	Shale & shells
200	280	Sand & gravel
280	370	Shale & shells
370	395	Red bed
395	423	Shale & red bed
423	520	Sand
520	555	Shale
555	595	Red bed & shale
595	865	Sandy shale
865	1170	Shale & red rock
1170	1740	Shale
1740	1800	Shale & anhydrite line
1880	2400	Line & shale
2400	2460	Shale & lime streaks
2460	2765	Shale & lime
2765	2870	Shaled lime streaks
2870	3330	Shale & lime
3330	3380	Line
3380	3595	Shale & lime
3595	3685	Line
3685	3854	Shale & lime
	3854	Rotary Total Depth

RECORDED
STATE OF KANSAS COMMISSION
AUG 22 1952
CONSERVATION DIVISION
Wichita, Kansas

Set 928' of 8-5/8", surface casing, cemented with 500 sacks.
Set 3848.50' of 5-1/2", cemented with 100 sacks.

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of Whinney #1, Section 34-21E-16N, Pawnee County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

By Gordon L. Koelling
Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 19th day of August, 1952.

Ada C. May
Notary Public

My commission expires August 31, 1955.