

15.145.00786.0001

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 76,168-C (D-11,782)

LEASE NAME Fairbanks

WELL NUMBER #2 SWD

2970 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 34 TWP. 21 RGE. 16 (E) or (W)

COUNTY Pawnee

Date Well Completed 11-17-64

Plugging Commenced 11-27-85

Plugging Completed 11-30-85

LEASE OPERATOR Hilliker Production

ADDRESS 5207 Telstar, Great Bend, Ks. 67530

PHONE# (316) 792 2788 OPERATORS LICENSE NO. 7230

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City District #1

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation POZ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	943	8 5/8	950	None
		0	3865	5 1/2	3865	None
	3847-	3910		4 1/2	63	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Spot thru tubing - 75 sxs (50-50) Poz., 3% CC, 100c# Flocc, 1 sk hulls 2343 ft. - 3048 ft.

Spot mud 975-2343, spot 25 sxs (50-50) Poz, 3% CC 740-975', spot mud 430' to 740', spot 50 sks. Cmt. at 430', spot 50 sks. cmt. 0' -430'. Cmt. circulated.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor HOWCO License No. 5287

Address 2400 Main street, Great Bend, Kansas, 67530

STATE OF Kansas COUNTY OF Barton, ss.

Joe Foelgner, Jr. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Joe Foelgner Jr.

(Address) 3315 - 16th Street, Great Bend, Ks.

SUBSCRIBED AND SWORN TO before me this 23rd day of January, 19 86



Loneita Barry
Notary Public

CONTRACTOR'S WELL LOG

COMPANY: Murgrove Petroleum Corporation
 CONTRACTOR: Murgrove Petroleum Corporation
 FIRM: Fairbanks #2
 LOCATION: SW SW NW Section 34-21-16
 Pawnee County, Kansas
 COMMENCED: November 11, 1952
 COMPLETED: November 24, 1952

0	120	Shale and Shells
120	130	Red Bed and Sand
130	285	Shale and Shells
285	315	Shale
315	375	Grey Shale and Sand Rock
375	415	Red Bed
415	615	Sand and Red Bed
615	875	Red Bed and Shale
875	913	Red Rock
913	995	Red Bed
995	1865	Shale and Shells
1865	3551	Shale and Lime
3551	3868	Lime
	3868	Rotary Total Depth

Set 8 5/8" cemented with 500 sacks of common cement.

Set 5 1/2" casing at 3868' cemented with 150 sacks of cement.

STATE OF KANSAS)
) SB
 COUNTY OF SEDGWICK)

I, GORDON L. KELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the Fairbanks #2, Section 34-21-16, Pawnee County, Kansas, as reflected by the files of Murgrove Petroleum Corporation.

MURGROVE PETROLEUM CORPORATION

By Gordon L. Kelling
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas this 1st day of December, 1952.

Mary L. Hann
 Notary Public

My Commission Expires: November 14, 1956.

RECEIVED
 STATE CORPORATIONS COMMISSION
 JAN 27 1986
 CONSERVATION DIVISION