

15.139.05466.0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Rice SEC. 16 TWP. 21 RGE. 7w E/W
 Location as in quarters or footage from lines:
NE SE NW

Locate Well
 correctly on above
 Section Platt.

Lease Owner K & K Oil
 Lease Name Stange #2 Well No. _____
 Office Address Box 347, Chase, Kansas 67524
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 6/6/83
 Plugging completed 7/15/83
 Reason for abandonment of well or producing formation
Depleted

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation _____ Depth to top _____ bottom _____ T.D. 3381'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				13	130'	none
				7"	3355'	2492'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Sanded bottom off to 3300' & ran 7 sacks cement. Shot pipe at 3005', 2727',
 and 2500'. Pulled total of 79 joints. Plugged well with 7 bulls, 25 gel, &
 150 sacks 50/50 poz 4% gel.

Plugging complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 19th day of July, 19 83

My Commission expires:



Irene Hoover
 RECEIVED Notary Public.
 STATE CORPORATION COMMISSION

JUL 22 1983

15.159.05466.0000

WELL BUREAU - KANSAS GEOLOGICAL SURVEY
412 Union National Bank Bldg, Wichita, Kan.

SUN FLOWER OIL CO.
Stange No. 2

SEC. 16 T. 21 R. 7W
NE SW NW

Total Depth. 3381
Comm. 4-22-37 Comp. 5-14-37
Shot or Treated.
Contractor.
Issued. 6-12-37

County Rice.



CASING.

13" 130 - *cc*
7" 3355' - *100 sf*

Elevation.

Production. Pot. 6023 B.

Figures Indicate Bottom of Formations.

sand and clay	60
red bed and shells	130
shells & red bed	430
shale grey	550
shale blue & shells	708
shale and shells	990
lime and shale	1068
anhydrite	1105
shale and shells	1202
red bed	1206
shells	1212
broken lime & shale	1316
broken lime	1400
lime	1416
lime and shale	1614
lime	1733
broken lime and shale	1839
lime	1867
shale and shells	1950
lime and shale	2 042
lime	2054
sand broken	2073
lime	2384
sand	2400
lime and shale	2424
lime and shale hard	2483
lime hard	2526
lime	2774
lime hard	2822
lime	2908
shale hard	2937
2937 equals 2933 S.L.M. Correction,	
shale and lime shells	3022
shale	3023
sand	3 036
lime brown	3078
lime broken	3179
lime brown	3202
lime broken	3288
lime	3334
lime and shale	3355
shale	3381

Total Depth.

RECEIVED
STATE CORPORATION COMMISSION

JUN 07 1983

CONSERVATION DIVISION
Wichita, Kansas