

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

McPherson County, Sec. 35 Twp. 21s Rge. 3W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SW NE SW

Lease Owner Oil Property Management
Lease Name Florian Well No. 1
Office Address 300 Insurance Bldg. Wichita Ks.
Character of Well (Completed as Oil, Gas or Dry Hole)

Dry hole

Date Well completed 6/15 1976
Application for plugging filed 1/18 1977
Application for plugging approved 1/20 1977
Plugging commenced 1/25 1977
Plugging completed 1/27 1977
Reason for abandonment of well or producing formation

Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Hugh Scot
Producing formation Miss Depth to top 3549 Bottom 3550 Total Depth of Well 3550
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	168	8 5/8		
		0	3549	4 1/2		1625

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sand and 4 sacks cement on bottom Bridge at 200' with 25 sacks cement
Bridge at 40 ft. 10 sacks filled to bottom of cellar

JAN 31 1977

Conservation Division
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Nicholas Casing Pulling, Geneseo, Kansas

STATE OF _____ COUNTY OF _____, ss.
(employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Nicholas

(Address)



Subscribed and sworn to before me this 28th day of January, 1977

Glenn M. Stegman
Glenn M. Stegman Notary Public.

My commission expires 7/6/77

DRILLERS LOG

No. 1 Florian

CASING RECORD:	COMPANY:	Patrick Petroleum Corporation	DESCRIPTION:
8 5/8' @ 168' w/125 sx cmt.	CONTRACTOR:	Red Tiger Drilling Company	SW NE SW Sec. 35-T21S-R3W McPherson County, Kansas
4 1/2" @ 3,548' w/150 sx cmt.	COMMENCED:	September 10, 1976	
TOTAL DEPTH: 3,550'	COMPLETED:	September 18, 1976	ELEVATION: 1,455' KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	24	
Sand	24	140	
Blue Shale	140	400	
Anhydrite & Shale	400	715	
Lime & Shale	715	2305	
Lime & Sand	2305	2590	
Lime & Shale	2590	2930	
Lime	2930	3045	
Mississippi	3045	3490	
Hunton Lime	3490	3550	
RTD		3550	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

Subscribed and sworn to before me this 21st day of September, 1976.

D'Ann Drennan
Notary Public

