


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas



Locate well correctly on above
Section Plat

McPherson County, Sec. 35 Twp. 21 Rge. 3 (E) (W)
Location as "NE/CNW/SW" or footage from lines SE/4
Lease Owner Independent Lease Management Company
Lease Name Krehbiel C#3 Well No.
Office Address Hutchinson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 10/8/68 19
Plugging completed 10/10/68 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Scott
Producing formation Depth to top Bottom Total Depth of Well 3595 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3595'	2965'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Worked tension to 11", shot pipe at 2983' and worked pipe loose.
Pulled 92 joints, loaded junk rack. Checked fluid to 240' and set rock bridge to 220', dumped 25 sacks of cement. Mudded to 40', set 10' rock bridge and dumped 10 sacks of cement.

PLUGGING COMPLETE.


RECEIVED
STATE CORPORATION COMMISSION
OCT 16 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT-CASING PULLING CO., INC.
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filled and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas (Address)

Subscribed and sworn to before me this 11th day of October, 1968



Margaret Melcher
Notary Public.

My commission expires February 15, 1971

BRUNSON PRODUCTION & EXPLORATION, INC.
WICHITA, KANSAS

WELL: KREHBIEL "C" # 3

CEL NW SE

COMMENCED RD: 9-9-57
COMPLETED RD: 9-20-57

35-21S-3W

TOTAL DEPTH: 3595'

MCPHERSON COUNTY

CASING: 210' 8 5/8" O.D. 28 1/2"
3595' 5 1/2" O.D. 14"

ELEVATION: 1459 K.B.

CONTRACTOR: BRUNSON
PRODUCTION & EXPLORATION, INC.

STRATA	DEPTH	TOPS
Surface Soil & Clay	22	Brown Lime 2386 (- 927)
Sand & Gravel	93	Lansing 2424 (- 965)
Shale	183	Mississippi Lime 3147 (-1688)
Clay	192	Kinderhook 3441 (-1982)
Lime	193	Hunton 3529 (-2070)
Shale	212	Maquoketa 3549 (-2090)
Shale, Clay & Shells	420	
Shale & Lime	640	
Broken Lime	1135	
Shale	1180	
Shale & Lime	1955	
Broken Lime	2230	
Shale & Lime	3136	
Lime, Shale & Chert	3261	
Lime & Chert	3288	
Lime, Chert & Shale	3386	
Lime	3458	
Shale & Lime	3580	
Lime, Shale & Sand	3595	
TOTAL DEPTH	3595	

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling report.

BRUNSON PRODUCTION & EXPLORATION, INC.
BY

Ralph B. McLaughlin
Ralph B. McLaughlin - Secretary-Treas.

Signed and sworn to in my presence this 27th day of September, 1957, by Ralph B. McLaughlin, Secretary-Treasurer of Brunson Production & Exploration, Inc., a Corporation in the State of Kansas.

Anna M. Wedan
Anna M. Wedan - Notary Public

My commission expires July 1, 1961.

RECEIVED
STATE CORPORATION COMMISSION
OCT 9 - 1968
CONSERVATION DIVISION
Wichita, Kansas