

15.113.04821.0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Major Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

McPherson County, Sec. 35 Twp. 21 Rge. 3 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NW 1/4 CS 1 SE NE
Lease Owner Independent Lease Management Company
Lease Name Goering "B" Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19____
Application for plugging filed 19____
Application for plugging approved 19____
Plugging commenced 8-11-66 19____
Plugging completed 8-15-66 19____
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation Depth to top Bottom Total Depth of Well 3533 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	179'	None
				5-1/2"	3529'	1284'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, pushed plug to 2941' and dumped 5 sacks of cement with dump bailer. Pulled 5 1/2" casing and pumped 80 sacks of cement to plug well.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
SEP 2 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of August, 1966

My commission expires May 20, 1968

Notary Public.

BRUNSON PRODUCTION & EXPLORATION, INC.
WICHITA, KANSAS

RECEIVED
STATE COMMISSION
AUG 15 1966

WELL: GOERING "B" # 1

COMMENCED RD: 6-4-57
COMPLETED RD: 6-11-57

TOTAL DEPTH: 3533'

CASING: 179' 8 5/8" O.D. 28 1/2"
3529' 5 1/2" O.D. 11 1/2"

CSL SE NE

35-21-3W

MCPHERSON COUNTY

ELEVATION: 1460

CONTRACTOR: BRUNSON
PRODUCTION & EXPLORATION, INC.

STRATA	DEPTH	TOPS
Surface Soil	30	Lansing 2423 - 963
Sand	120	Mississippi Formation 3127 - 1667
Shale & Clay	160	Kinderhook Shale 3432 - 1972
Shale	183	Miscner NONE
Shale & Clay	460	Hunton 3529 - 2069
Lime & Shale	660	
Anhydrite	700	
Shale	820	
Shale & Shells	1020	
Shale & Lime	1255	
Shale	1830	
Shale & Lime	3155	
Lime & Chert	3336	
Lime & Shale	3412	
Lime	3433	
Shale & Lime	3533	
Total Depth	3533	

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling report.

BRUNSON PRODUCTION & EXPLORATION, INC.
BY

Ralph B. McLaughlin
Ralph B. McLaughlin, Secretary-Treasurer

Signed and sworn to in my presence this 27th day of June, 1957, by
Ralph B. McLaughlin, Secretary-Treasurer of Brunson Production &
Exploration, Inc., a Corporation in the State of Kansas.

Wanda Lou Bruce
Wanda Lou Bruce-Notary Public

My commission expires March 6, 1961.