


STATE OF KANSAS
STATE CORPORATION COMMISSION

2
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

McPherson County, Sec. 35 Twp. 21 Rge. 3 (E) W (W)
Location as "NE/CNW/SW" or footage from lines. C NE/4
Lease Owner Independent Lease Management Company
Lease Name Goering "B" Well No. 4
Office Address Wichita, Kansas JUN 3 1963
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 5-22-63 19
Plugging completed 5-27-63 19
Reason for abandonment of well or producing formation Depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Cecil Jones
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3545 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	206'	None
				5-1/2"	3545'	2960'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3540', sanded to 3530' and dumped 5 sacks of cement @ 3530' with dump bailer. Pulled 5 1/2" casing. Set rock bridge from 200' to 185' and dumped 2 1/2 yards of ready-mix cement from 185' to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING COMPLETE.

JUN 27 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of May, 1963

My commission expires May 20, 1964

Milton J. Volin
Notary Public.



BRUNSON PRODUCTION & EXPLORATION, INC.
WICHITA, KANSAS

WELL: GOERING "B" #4

C NE/4

COMMENCED RD: 5- 2-58

35-21S-3W

COMPLETED RD: 5-11-58

McPHERSON COUNTY, KANSAS

TOTAL DEPTH: 3545'

3545' 5 1/2", 100 sacks cement ELEVATION: 1458 DF

CASING: 206' 8-5/8"

125 sx cement.

CONTRACTOR: Brunson Prod. & Explor.

STRATA	DEPTH	TOPS	
Surface Soil	15	Mississippi	3130 (-1669)
Clay	25	Kinderhook	3425 (-1964)
Sand	130	Hunton	3527 (-2066)
Clay, Shale & Shells	450	Maquoketa	3541 (-2080)
Lime & Shale	805		
Red Shale	825		
Lime & Shale	930		
Lime	1060		
Lime & Shale	1365		
Lime streaks & Shale	1740		
Shale & Lime	2562		
Sand	2587		
Lime & Shale	2630		
Lime	3025		
Lime & Shale	3190		
Lime & Chert	3343		
Lime	3425		
Shale	3545		
Total Depth	3545		

RECEIVED
STATE CORPORATION COMMISSION

MAY 20 1963

CONSERVATION DEPT
Wichita, Kansas

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling report

BRUNSON PRODUCTION & EXPLORATION, INC.,

Ralph B. McLaughlin

 Ralph B. McLaughlin

Signed and sworn to in my presence this 13th day of June, 1958, by Ralph B. McLaughlin, Secretary-Treasurer of the Brunson Production & Exploration, Inc., a Corporation of the State of Kansas.

Mary G. LaFollette

 Mary G. LaFollette, Notary Public

My commission expires June 16, 1959.