

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

McPherson County, Sec. 35 Twp. 21 Rge. 3 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines SE NE NE

Lease Owner Independent Lease Management Company

Lease Name Goering "B" Well No. 2

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 6-23-64 19

Plugging completed 7-2-64 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well 3545 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	202'	None
				5-1/2"	3528'	2213'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3545', sanded to 3515' and dumped 5 sacks of cement @ 3515' with dump bailer. Pulled 5 1/2" casing, checked fluid to 217', set rock bridge to 185' and dumped 2 1/2 yards of ready mix cement to base of cellar.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

JUL 14 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY

Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss. Noel J. Knight

(employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

Chase, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of July, 1964

My commission expires May 20, 1968

Milton J. Volin Notary Public.

BRUNSON PRODUCTION & EXPLORATION, INC.
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUN 25 1964

CONSERVATION DIVISION
Wichita, Kansas

WELL GOERING "B" #2

O.E.L. NE/4

COMMENCED RD: 4-9-58
COMPLETED RD: 4-19-58

35-218-3W

TOTAL DEPTH: 3545'

McPHERSON COUNTY, KANSAS

CASING: 202' - 8-5/8" 28# *185# cement*
Used.

ELEVATION: 1461 RB

CONTRACTOR: Brunson P. & E., Inc.

STRATA	DEPTH	TOPS
Surface Soil & Clay	20	Lansing 2426 (-1965)
Sand & Gravel	125	Mississippi Lime 3127 (-1666)
Clay & Shale	160	Kinderhook 3426 (-1965)
Shale & Shells	200	Misener Sand 3525 (-2064)
Shale & Clay	308	Hunton 3527 (-2066)
Shale & Shells	460	Maquoketa Dolomite 3536 (-2075)
Lime	510	
Lime & Shale	715	
Sandy Shale	740	
Chalk & Lime	790	
Red Shale	815	
Lime	830	
Shale	875	
Lime & Shale	1180	
Shale w/ Lime Streaks	1695	
Shale & Lime	2050	
Lime	2150	
Shale & Lime	2260	
Sand Shale	2355	
Shale & Lime	2605	
Lime	2770	
Sand	2785	
Lime	3020	
Lime & Shale	3130	
Lime & Chert	3242	
Chert	3273	
Lime & Chert	3379	
Lime	3427	
Shale	3525	
Lime	3545	
Total Depth	3545	

14# used
100# cement
5 1/2' set @ 3528'
Plug @ 3520
Core H-40 I believe

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling report.

BRUNSON PRODUCTION & EXPLORATION, INC.,

By

Ralph B. McLaughlin
Ralph B. McLaughlin

Signed and sworn to in my presence this 29th day of April, 1958, by Ralph B. McLaughlin, Secretary-Treasurer of the Brunson Production & Exploration, Inc., a Corporation of the State of Kansas.

Mary G. LaFollette
Mary G. LaFollette, Notary Public

My commission expires June 16, 1959.