


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

County. Sec. 35 Twp. 21 Rge. 3 (E-W) (N-S)
Location as "NE/CNW/SW" or footage from lines C. SE, SE-SW.
Lease Owner E. K. Carey Contractor.
Lease Name Kreibel Well No. 1
Office Address Box 620 McPherson, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 1-20-56 1956
Application for plugging filed 3-15-61 1961
Application for plugging approved 3-15-61 1961
Plugging commenced April 20 1961
Plugging completed May 6 1961
Reason for abandonment of well or producing formation NOT enough oil to produce
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Cecil Jones
Producing formation HUNTON Depth to top 355' Bottom 3556' Total Depth of Well 3556' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	295	NONE.
				5 1/2	3552.5	2417'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled back with sand and dumped 5 sacks of cement. Shot pipe off at 2417'. Pulled pipe and mudded hole to 260'. Set rock bridge and dumped 22 sacks of cement. Finished mudding hole to 30'. Set rock bridge and dumped 8 sacks of cement at base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor BERT SELF
Address RR 4 HUTCHINSON, KS.

STATE OF Kans., COUNTY OF Reno, ss.
Employee (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self

R. R. #4, Hutchinson, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of May, 1961

My commission expires August 12, 1961

Dorothy Self
Notary Public.

E. F. Carey Contractor
Box 520
McPherson, Kansas

Elevations: 1450 W.B.
1456 D.F.
1454 Cr.

Well No. 1

8-5/8" x 5 1/2" Head 7.15'
below F. B.

C, SE 34 SW,
Sec. 35-21-34
McPherson County, Kansas

Casing Record:

8-5/8" 298' w/225 sks
Portmix cement and 400% cc.

5-1/2" ^{3552.50}
~~3552.50~~ w/20 sks.
Regular Cement and 40 sks.
Portmix.

Well Commenced: 12-18-55
Well Completed: 1-3-56

Contractor: E. F. Carey Contractor, Box 520, McPherson, Kansas
Geologist: Don Hollar, E. F. Carey, Inc., 515 Central Bldg. Wichita

Figures Indicate Bottom of Formation K. 1.

lar and base	0
	30
	100
le and shells	256
le and shale	296
le and shells	405
le and shale	900
le and lime	910
le and shale	1100
le and lime	1730
le and shale	1905
	2220
ly lime and shale	2300
le	2370
	2420
le	2430
	2700
le and shale	3040
le and lime	3150
le	3152
s. lime	3295
le and chert	3357
	3445
le	3547
ner sand	3551
ton	3556 TD

Geologist Tops:

Lansing	2460
Mississippi	3152
Levee Pass.	3447
Turton	3551

Potary Total Depth 3556

Set 5 1/2" casing ^{3552.50}
~~3552.50~~ or 3 1/2' off
bottom.

DET - 3549-3556' or 7' anchor. Tool
open 30 min. with strong blow thru
cut test. Closed 20 min. for HP.
Recovered 2090' gas, 100' gassy muddy
oil and 20' water. OHP 722.

RECEIVED
STATE COMMISSION

1956

CONSERVATION DIVISION
Wichita, Kansas

This is to certify that the above information is to the best of my
knowledge true and correct.

WITNESSED AT _____ to before me this 4th day of January, 1956

E. F. CAREY CONTRACTOR

BY Herbert Shotton
Herbert Shotton, Superintendent

Attest:

My Commission Expires: November 13, 1956