


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

McPherson

County. Sec. 4 Twp 21 Rge. 3 (E) W (W)

Location as "NE/CNW/SE" or footage from lines SW SW SE

Lease Owner Chas. E. Petrey

Lease Name Hrehbiel "B" Well No. 2

Office Address 1300 N. Maple, McPherson Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil well

Date well completed 11-5 1954

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced May 31 1957

Plugging completed June 8 1957

Reason for abandonment of well or producing formation Non-Commercial

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Depth to top 3244' Bottom 3285' Total Depth of Well 3380' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	254'	None
				5 1/2"	3379'	2684'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Build rock bridge to 3235

Dump 6 sack cement plug at 3235'

Shot 5 1/2" casing loose at 2684' & pulled same.

Mudded hole - Bailed down to 300'

Set rock bridge at 300'

Dumped 25 sack cement plug at 300' to 175'

Mudded hole fro, 175' to 20'

Dumped 5 sack cement plug from 20' to bottom of collar.

Job completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Wiggins & Lamb Pipe Pulling Co.

Address P.O. Box 191, McPherson Kansas

STATE OF Kansas, COUNTY OF McPherson, ss.

Charles E. Petrey (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Chas. E. Petrey
1300 N. Maple, McPherson Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of June, 1957

My commission expires Jan 17, 1961

Carroll D. Henslow
RECEIVED Notary Public.
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 4 T. 21 R. 3W
BOOK PAGE 16 LINE 12

JUN 18 1957 6-18-57
CONSERVATION DIVISION
Wichita, Kansas

Chas
Peterson

15-113-19257-0000

BRUNSON PRODUCTION & EXPLORATION, INC.

WELL: B KREHBIEL # 2
COMMENCED RD: 10-26-55
COMPLETED RD: 11-5-55

SW SE SE APPROX.
SEC: 4-21-3

TOTAL DEPTH: 3380'

McPHERSON COUNTY

CSG: 252 1/2' 8 3/8" OD 25 1/2" # 145 Ash Cement
3380' 5 1/2" OD 14# 8 rn thd 100 " "

ELEVATION; 1450 RB

CONTRACTOR: BRUNSON
PROD. & EXPLORATION

STRATA	DEPTH	TOPS
Surface Soil & clay	20	Mississippi 2953-1503
Sand & Gravel	205	Viola 3238-1788
Shale	390	Simp. Shale 3267-1817
Lime	646	Simp. Sand 3271-1821
Shale	656	Arbuckle 3340-1890
Lime	1200	
Lime & Shale	1482	
Shale & Lime	1922	
Broken Lime	2120	
Shale & Lime	2207	
Shale	2296	
Lime & Shale	2342	
Shale	2365	
Lime & Shale	2390	
Broken Lime	2495	
Lime & Shale	2662	
Lime	2763	
Shale	2950	
Chert & Lime	2993	
Shale	3003	
Sand & Shale	3238	
Lime, Chert & Sand	3251	
Lime, Chert & Shale	3267	
Lime, Shale & Sand	3273	
Sand	3323	
Shale & Lime	3337	
Lime	3380	
Total Depth	3380	

RECEIVED
STATE CORPORATION COMMISSION

JUN 18 1957

CONSERVATION DIVISION
AM. 7325

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

BRUNSON PRODUCTION & EXPLORATION, INC.
BY

Ralph B. McLaughlin
Ralph B. McLaughlin - Sec. Treas.

Signed and sworn to in my presence this 8th day of November, 1955, by Ralph B. McLaughlin, Secretary-Treasurer of the Brunson Production & Exploration Company, Inc., a Corporation in the State of Kansas.

Donna L. Riley
Donna L. Riley - Notary Public

My commission expires December 31, 1958.

PLUGGING
FILE SEC. 4 T. 21 S. 3W
BOOK PAGE 16 LINE 12