

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-113-04665-0000

API NUMBER N/A

LEASE NAME Krehbiel

WELL NUMBER 4

1650 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 4 TWP. 21S RGE. 3 (XXXX)(W)

COUNTY McPherson

Date Well Completed 6-4-90

Plugging Commenced 8-17-91

Plugging Completed 8-17-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Liedtke Operating Corporation

ADDRESS 370 17th St., Suite 5020, Denver CO 80202

PHONE#(303) 595-8405 OPERATORS LICENSE NO. 20385

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-6-91 (date)

by Maurice Korpaga (John Sanders, Field Agent) (KCC District Agent's Name).

Is ACO-1 filled? N/A If not, is well log attached? N/A

Producing Formation Arbuckle Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
Cenozoic deposits	water	30'	90'	15 1/2"	176'	none
				12 1/2"	3000+'	none
Simpson & Arbuckle	oil and gas	3360'	3388'	8-5/8"	3283'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Perf. 4 shots @ 600', 4 shots @ 375'. 2 sks. hulls, 50 sks. common, 4% C.C. thru tubing @ 3040'. gel spacer thru tubing to 600'. 50 sks. common, 4% C.C. thru tubing @ 600'. Tubing @ 370', pump 400 sks. 60-40 poz mix, 4% gel. Reached pressure. Pull tubing. Put on swage to 8-5/8", pump 100 sks. 60-40 poz mix, 4% gel, cement circ. inside and outside 15 1/2". Bull head
(If additional description is necessary, use BACK of this form.) (over)

Name of Plugging Contractor Chase Well Service, Inc. License No. 6123

Address P. O. Box 355, Great Bend, Kansas 67530


STATE OF KANSAS COUNTY OF BARTON, ss.

Charles W. Steincamp (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Charles W. Steincamp

(Address) P. O. Box 355, Great Bend KS 67530

SUBSCRIBED AND SWORN TO before me this 29th day of August, 19 91



Loneita Barry
Loneita Barry Notary Public

My Commission Expires: _____

5 sks. into 12 $\frac{1}{4}$ " 500 lbs. pressure. Fill cellar 2' cement. Fill 8-5/8" casing to surface from top.

8-19-91 Pipe filled to surface w/bulk cement.