

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

909

McPherson

County. Sec. 4 Twp. 21S Rge. (E) 3 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. Se/4 SE/4 SW/4

Lease Owner Gulf Oil Corporation

Lease Name Katie Well No. 1

Office Address Box 661, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Oil well

Date, well completed 5-17-30 19

Application for plugging filed 6-3-41 19

Application for plugging approved 6-3-41 19

Plugging Commenced 6-4-41 19

Plugging Completed 6-7-41 19

Reason for abandonment of well or producing formation Oil reserves depleted.

If a producing well is abandoned, date of last production January 31 1941

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durke, McPherson, Kansas

Producing formation Wilcox Sand Depth to top 3458' Bottom 3469' Total Depth of Well 3610' Feet  
FB 3469'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				15-1/2"	206'	None
				8-1/4"	3381'	1895'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with mud to 3381', dumped 6 sacks cement 3381' to 3362'. Filled with mud to 2500'. Ripped 8-1/4" casing at 2100', 2000', and 1880', recovered 83 joints casing. Filled hole with heavy mud to 216'. Set bridge at 216' and filled hole with rock to 206'. Dumped 20 sacks cement from 206' to 186'. Filled hole with mud from 186' to 14'. Capped with 14 sacks of cement.

PLUGGING  
FILE OF 4. 21.8 SW  
BOOK PAGE 140 LINE 31

JUN 14 1941  
STATE CORP. COM.  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Gulf Oil Corporation

Address Box 661, Tulsa, Oklahoma

STATE OF Kansas, COUNTY OF Rice, ss.

O. L. Stevenson

(employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) O. L. Stevenson

(Address)

SUBSCRIBED AND SWORN to before me this 11<sup>th</sup> day of June, 1941

My commission expires January 3, 1945

Jackson E. Watkins  
Notary Public.

# WELL RECORD

WELL NO. (2) One LEASE Katie

COMPANY Gypsy Oil Co.

AUTH. K-1284

DATE—Drilling Began 1-27-30

Well Completed 5-17-30

First Production 3-6-30

SHOT—Date -- With

Quarts—From

To

By

SAND RECORD Wilcox Sand 3458' to 3469'

DEPTH 3469'

PLUGGED BACK FROM 3610'

INITIAL PRODUCTION\* "P" 60.00 barrels.

## CASING RECORD

Size	Wt.	Thd.	Class	Make	Run	Sacks Cement	Pounds Cal. Chlo.	Pulled	Left In
15 1/2	70	10	SH	S. S.	206	200	300		206
8 1/2	32	10	SH	S.S & LW	3381	500	600		3381
6-5/8	24	10	SH	S. S.	3484	-	-	3484	<del>3484</del>

S 4 T 21S R 3W

McPherson County,					
Kansas.					

(\*). Best Day; "F", Flowing Naturally; "L", Air-Gas Lift; "S", Swabbing; "P", Pumping.

ELEVATION 1474'

**PLUGGING**  
 FILE # 4-2LR3W  
 BOOK PAGE 140 LINE 31



