



WELL LOG

15. 113. 04679. 0005

Lease:- A. E. Morehouse # 10
 NW/4 - NE/4 & E/2 of NE/4
 Sec. 4-21S-3W

Surface Soil	20'
Sand & Gravel	45'
Mud	65'
Gravel	95'
Shale	468'
Shale & Shells	1035'
Shale	1745'
Lime	1770'
Shale	1816'
Shale & Lime	2014'
Hard Shale & Sand	2108'
Shale & Lime	2183'
Sand	2211'
Shale & Lime	2351'
Sticky Shale	2370'
Lime	2391'
Sandy Lime	2497'
Sandy Lime & Shale	2537'
Lime	2553'
Shale	2601'
Shale & Lime	2624'
Lime	2674'
Sandy Lime	2697'
Lime & Shale	2758'
Lime	2813'
Shale	2993'
Lime	3013'
Shale & Lime	3038'
Shale	3228'
Viola Lime	3270'
Green Shale	3277'
Wilcox Sand	3305'
Sandy Shale	3336'
Green Shale Break	3340'
Silicious Lime	3351' Orig. T. D.

Plugged back from 3351' to 3338' 6/1/31 with Lead wool & Putty.

Plugged back from 3338' to 3325' 10/16/31 with Steel cuttings & Lead wool.

Plugged back from 3323' to 3310' 12/5/31 with Lead wool cuttings & Tin.

2/1/33 Cleaned out to 3329' and Plugged back to 3314' w/Lead wool & cuttings.

10-25-33 Cleaned out from 3245' to 3314' and plugged back from 3314' to 3312' with Lead wool, Oakum & 20" of Solid Lead Plug.

