

STATE OF KANSAS
STATE CORPORATION COMMISSION

**Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bistling Building
Wichita, Kansas**

WELL PLUGGING RECORD

OR

**Strike out upper line
when reporting plug-
ging off formations.**

McPherson County. Sec. **4** Twp **21S** Rge. **(E)** **3** (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. **SE NE**

Lease Owner. **Sinclair Prairie Oil Co**

Lease Name A.E. Morehouse

Office Address..... Bx 521, Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Oilwell

Date well completed..... May 1, 1930 19

Application for plugging filed verbally, then by mail on Jan 21, 1947 19

Application for plugging approved.....19.....

Plugging commenced..... Jan 15, 1947 19

Plugging completed..... Jan 19, 1947 19.....

Reason for abandonment of well or producing formation prodn exhausted

If a producing well is abandoned, date of last production..... **June 1946** 19.....

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes, verbal permission

Name of Conservation Agent who supervised plugging of this well..... Ruel Durkee

Producing formation Arbuckle Depth to top 3453 Bottom Total Depth of Well 3457 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.



3457-3000' gravel & cement.

3000-225' mid

225-200' cement 30 sx

200-15' mud

15'-base cellar cement 10 sx



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to E.H. Gibbons

Address..... Bx 774 Great Bend, Kas

STATE OF Kansas, COUNTY OF Barton ss.

I, E.H. Gibbons

(employee of owner) or ~~(owner or operator)~~ of the above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Bx 774 Great Bend, Kasn

(Address)

SUBSCRIBED AND SWORN to before me this 25th day of January, 1947

My commission expires _____



Sinclair Prairie Oil Co.

Well Log

A.E. Morehouse # 1
 Sec. 4-23S-3W, McPherson Co., Kas.

Drilling begun Apr 6, 1930.
 " comp May 1, 1930
 TD 3433' Later deepened to 3457'

Surface Soils	129	
Shale & Lime Shells	329	
Soapstone, Lime	620	
Shale	720	
Lime sand	800	
Shale	900	
Lime	950	129' of 15 $\frac{1}{2}$ "
Lime Shells	1040	3379' of 8 $\frac{1}{4}$ "
Sandy Shale	1260	
Shale, Lime	1470	
Lime	1500	
Shale	1760	
Lime-hard	1800	
Shale-sticky	1880	
Lime-chalky	1920	
Lime-sandy	1950	
Shale-sticky	2040	
Lime-hard sandy	2100	
Shale & Shells	2220	
Lime-hard	3210	
Shale	2400	
Lime-broken	2490	
Lime	2580	
Kas City Lime	2610	
Lime	2630	
Kas City Lime	2670	
Lime	2820	
Sandy Shale	2850	
Gyp Rock & Shale	2910	
Sandy Shale	2970	
Shale	3000	
White Chalk	3030	
Chat	3060	
Lime & Chat	3090	
Lime	3120	
Lime red rock	3170	
Shale	3210	
Shale-sticky	3250	
Slate & Shale	3300	
Shale	3375	
Viola Lime	3395	
Wilcox Sand -top 3395'	3433	
" "	3446	
Green Shale	3453	
Arbuckle Lime	3457'	TD

FILE

4 21 30
 94 7

STATE OF KANSAS
 COMMISSIONER

JAN 23 1947

OFFICE