


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

McPherson County, Sec. 17 Twp. 21 Rge. 1 (E) (W) W.

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines _____
Lease Owner John Lindas Oil, Inc.
Lease Name Goering Well No. 1
Office Address 701 Rule Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 11 19 51
Application for plugging filed December 13 19 51
Application for plugging approved December 11 19 51
Plugging commenced January 5 19 55
Plugging completed January 12 19 55
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3448' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	222'	None
				5 1/2"	3322'	2570

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Lane-Wells plug @ 3071' Perforated w/ 15 shots from 2968' to 2971'. Set a plug @ 2960' Solid w/ crushed rock and Gal Seal & cement. Top of same @ 2950.
Filled hole w/ heavy mud to 210 Set solid plug & 15 sacks cement. Filled hole w/ mud to 15' and set solid plug and 5 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Morgan Pipe Pulling Co.
Address Hutchinson, Kansas

STATE OF KANSAS, COUNTY OF McPHERSON, ss.
Tom Lummery (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Tom Lummery
701 Rule Bldg, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of January, 19 55
Catherine Ransley
Notary Public.

My commission expires March 25, 1956

PLUGGING
FILE REC 17 21 R 1W
BOOK PAGE 84 LINE 31

1-21-55

JOHN LINDAS OIL COMPANY

#1 GOERING "B"

Total Depth: 3322'

Comm: 9-20-54

Comp: 10-1-54

Casing:

231' - 8-5/8" Surface Pipe cemented with 150 sks. cement.

3322' - 5 1/2" Casing cemented with 125 sks. cement.

NW NW SE, Sec. 17-21-1W, McPherson County, Kansas

Contractor: L. C. Smitherman Drilg. Co.

231 - 350	Lime & shale
350 - 550	Lime & shale
550 - 700	Lime & shale
700 - 790	Redbed, lime & shale
790 - 1010	Lime & shale
1010 - 1305	Lime & shale
1305 - 1620	Lime & shale
1620 - 1830	Lime & shale
1830 - 1965	Lime & shale
1965 - 2015	Lime
2015 - 2195	Lime & shale
2195 - 2225	Shale & lime
2225 - 2360	Lime
2360 - 2415	Lime
2415 - 2448	Shale & lime
2448 - 2529	Lime & shale
2529 - 2554	Lime
2554 - 2610	Lime
2610 - 2657	Lime
2647 - 2720	Lime & shale
2720 - 2800	Lime & shale
2800 - 2855	Shale & lime
2855 - 2935	Lime
2935 - 2975	Lime - Mississippi
2975 - 2980	Lime
2980 - 3042	Lime
3042 - 3081	Lime
3081 - 3111	Lime
3111 - 3149	Lime
3149 - 3185	Lime
3185 - 3197	Lime
3197 - 3215	Lime & shale
3215 - 3307	Lime & shale
3307 - 3320	Shale
3320 - 3322	Lime
3322	Total Depth.

We hereby certify that the above and foregoing is a true and correct copy of the Log on the #1 Goering "B", in NW NW SE, Section 17-21-1W, McPherson County, Kansas.

L. C. Smitherman Drilling Company

By [Signature]
L. C. Smitherman

Subscribed and sworn to before me this 11th day of October 1954.

[Signature]
Notary Public

My commission expires August 27, 1955.

PLUGGING
WELL SEC 17-21-1W
BOOK PAGE 87 LINE 21