



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

JAN 4 1973

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Parks of M.L. Brown has this
date requested permission to plug the following described well:

Mr. Parks guarantees payment of the plugging fee.

Operator's full Name: Maurice L. Brown

Complete Address: 1500 Vickers Bldg., Wichita, Kansas

Lease Name: Crist Well No. 1

Location: C SE SE Sec. 25 Twp. 21 Rge. 34 (E) (W)

County: Finney Total Depth 4808' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Parks was instructed to plug the well as follows:

8 5/8" to 366' circulated w/ cement. Mud 4808' to 700'

Spot 35 sacks cement 700' to 600' Mud 600' to 350'

Spot 30 sacks cement 350' to 250' Mud 250' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Edgar J. Evers
Conservation Division Agent