

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

15-055-10147-00-01

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 3-17-48 (of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Petroleum Production Management, Inc. OPERATORS LICENSE NO. 6234

ADDRESS 209 E. William, Suite 200, Wichita, KS 67202 PHONE # (316) 265-4651

LEASE (FARM) Lockman WELL NO. 1 WELL LOCATION SE SE SE COUNTY Finney

SEC. 22 TWP. 21 RGE. 34 (X) or (W) TOTAL DEPTH 4750 PLUG BACK TD 4155

Check One:

OIL WELL _____ GAS WELL _____ D & A _____ SWD or INJ WELL X DOCKET NO. (C-9,245) 68,315C

SURFACE CASING SIZE 8 5/8 SET AT 260 CEMENTED WITH 150 SACKS

CASING SIZE 5 1/2 SET AT 4650 CEMENTED WITH 220 SACKS

2 7/8 SET AT 4240 CEMENTED WITH 445 SACKS

PERFORATED AT 1900-1901 (squeeze w/600 sx) 1250-1251 (cem. w/128 sx - circ.)

5 1/2 Perf. at 4276-4285 (Marmaton) BP @ 4340. Miss. perfs 4614-4622.

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK X JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Run 1" tbg. down 5 1/2" - 8 5/8" annulus to 600'. Cement to surface w/100 sx. cl. H. Run 1" inside 2 7/8" to 1300' & cement with 35 sx. to surface.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? No
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Steve Park

PHONE # (316) 265-4651

ADDRESS 209 E. William, Suite 200, Wichita, KS 67202

PLUGGING CONTRACTOR Halliburton Services

LICENSE NO. _____

ADDRESS RECEIVED Liberal, KS

PHONE # (316) 624-3879

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT

SIGNED: Steve Park

(Operator or Agent)

DATE: 3-27-90

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

MAR 28 1990

3-28-90

①



Kansas Corporation Commission

MIKE HAYDEN	GOVERNOR
KEITH R. HENLEY	CHAIRMAN
RICH KOWALEWSKI	COMMISSIONER
JACK SHRIVER	COMMISSIONER
JUDITH MCCONNELL	EXECUTIVE DIRECTOR
FRANK A. CARO, JR.	GENERAL COUNSEL

CONSERVATION DIVISION
 SHARI FEIST ALBRECHT, DIRECTOR
 200 Colorado Derby Bldg.
 202 W. 1st Street
 Wichita, KS 67202-1286
 (316) 263-3238

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

July 18, 1990

Petroleum Production Management, Inc.
 209 E. William, Ste. 200
 Wichita, KS 67202

Lockman #1
 SE SE SE 22-21-34W
 Finney County, KS

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams

David P. Williams
 Production Supervisor

District: #1, 304 W. McArtor
 Dodge City, KS 67801