

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 17 1966

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Kaiser-Francis

Complete Address: 909 Palace Bldg., Tulsa, Oklahoma

Lease Name Applegate Well No. # 5

Location C N/2 NE NE Sec. 35 Twp. 21 Rge. 13 (E) (W) W

County Stafford County Total Depth 3672'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Southwest Casing Pulling Company

Address: Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 2:00PM Day 15th Month August Year 1966

The Above well was plugged as follows:

278' of 8 5/8" surface pipe, cemented with 200 sacks. 3667' of 5 1/2" long string, cemented with 125 sacks. This is an open hole. Bottom of the hole was sanded to 3650', and cemented with 5 sacks, through the dump bailer. 2750' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 270', rock bridge from 270' to 260', 1 sack of Cal-Seal and 1 sack of cement was mixed in a barrel, and put on plug at 260', through the dump bailer, and let set over-night. Next day hole was bailed dry, and filled with 3 1/2 Yards of ready-mix cement from 250' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/17/66
INV. NO. 3795-u

Signed: Archie Elving
Well Plugging Supervisor