

15.185.01827.0000

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAY 18 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Socony Mobil Oil Company, Inc.

Complete Address: 300 N. Broadway, Wichita, Kansas

Lease Name R. C. Gates Well No. # 5

Location SW SW NW Sec. 35 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3665'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 10:30AM Day 17th Month May Year 1965

The Above well was plugged as follows:

280' of 8 5/8" surface pipe, cemented with 300 sacks. 3658' of 5 1/2" long  
string, cemented with 150 sacks. This is an open hole. Bottom of the hole  
was sanded to 3590', and cemented with 5 sacks. 1830' of 5 1/2" long string  
was recovered from the hole. Fluid level was up in the hole. Bridge plug  
was pushed in fluid to 200', and 10' of rock bridge on plug. 5 sacks of  
cement was mixed in barrel, and put on plug at 190', through the dump  
bailer, and let set over-night. Next morning hole was bailed dry, and 20  
sacks of cement was added to the plug. Hole was filled with mud to 40',  
and 10' of rock bridge, and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 5/18/65

INV. NO. 1174-W