

15.185.01841.0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 12 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Sohio Petroleum Company

Complete Address: Box 673, Russell, Kansas

Lease Name Drach Well No. # 1

Location NW NW SW Sec. 35 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3672'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 1:30 PM Day 9th Month July Year 1965

The Above well was plugged as follows:

237' of 8 5/8" surface pipe, cemented with 190 sacks. 3670' of 5 1/2" long string, cemented with 120 sacks. Plug back to 3540'. Top perferation 3364'. Plug was pushed to 3355', and 50' of sand, and cemented with 5 sacks. 2695' of 5 1/2" long string was recovered from the hole. Fluid was up in the hole. Bridge plug was pushed in fluid to 237', and 10' of rock bridged on plug, 5 sacks of cement was mixed in barrel, and put on plug at 227', through the dump bailer, and let set over-night. Next morning hole was bailed dry, and 20 sacks of cement was added to the plug. Hole was filled with mud to 40', and 10' of rock bridge, and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 7-12-65
INV. NO. 1429-W

Signed: Archie Elving
Well Plugging Supervisor