



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Mobil Oil Corporation
Complete Address Box 1934 Oklahoma City, OK
Lease Name Mattie Gates B Well No. 2
Location SW/SE/SE Sec. 35 Twp. 21 Rge. 13 (E) (W) W
County Stafford Total Depth 3740
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Glen Pipe Pulling Co
Address Box 156 Ellinwood, KS License No. 686
Operation Completed: Hour 10:00 AM Day 1 Month 2 Year 1974

The above well was plugged as follows:

252 ft 8 5/8 surface cement circulated. 3739 ft 5 1/2 long string
cemented with 150 sacks. Top perf. 3366 ft. Sand to 3300 ft, 5 sacks
cement with bailer. Pulled 1600 ft 5 1/2. Pump 2 sacks hulls, 10 sacks
gel, 100 sacks cement to surface.

Pumped by Halliburton Cementing Co Great Bend, KS

RECEIVED
STATE CORPORATION COMMISSION
FEB 4 1974
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 2/5/74

INV. NO. 8513-W