

KANSAS

Form CP-3
Rev. 6-4-68STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTJ. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Mobil Oil Corporation
 Complete Address Box 1934 Oklahoma City, OK
 Lease Name Mattie Gates B Well No. 1
 Location SE/SE/SE Sec. 35 Twp. 21 S Rge. 13 (E) (W) W
 County Stafford Total Depth 3740
 Abandoned Oil Well Gas Well Input Well X SWD Well D & A
 Other well as hereafter indicated
 Plugging Contractor Glen Pipe Pulling Co
 Address Box 156 Ellinwood, KS License No. 686
 Operation Completed: Hour 9:00 AM Day 1 Month 2 Year 1974

The above well was plugged as follows:

276 ft 10 3/4 surface cement circulated. 3716 ft 5 1/2 long string
cemented with 150 sacks. Top perf. 3320 ft. Sand to 3300 ft, 5 sacks
cement with bailer. Pulled 2600 ft 5 1/2. Pump 4 sacks hulls, 20 sacks
gel, 150 sacks cement to surface.

Pumped by Halliburton Cementing Co. Great Bend, KSRECEIVED
STATE CORPORATION COMMISSION

FEB 4 1974

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 2/5/74
INV. NO. 8512-WSigned: [Signature]
Well Plugging Supervisor