

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Mobil Oil Corporation

Complete Address Box 1934 Oklahoma City, OK

Lease Name Mattie Gates B Well No. 8

Location SE/SW/SE Sec. 35 Twp. 21S Rge. 13 (E) W

County Stafford Total Depth 3745

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Glen Pipe Pulling Co

Address Box 156 Ellinwood, KS License No. 686

Operation Completed: Hour 2:00 PM Day 1 Month 2 Year 1974

The above well was plugged as follows:

276 ft 8 5/8 surface cement circulated. 3744 ft 5 1/2 long string

cemented with 150 sacks. Open hole. Sand to 3300 ft, 5 sacks cement

with bailer. Pulled 2017 ft 5 1/2. Pump 2 sacks hulls, 10 sacks gel,

100 sacks cement to surface.

Pumped by Halliburton Cementing Co Great Bend, KS

RECEIVED
STATE CORPORATION COMMISSION
FEB 4 1974
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/5/74

INV. NO. 8516-W

Signed: [Signature]
Well Plugging Supervisor