

15.125.01834.0000



Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Mobil Oil Corporation

Complete Address Box 1934 Oklahoma City, OK

Lease Name Mattie Gates B Well No. 3

Location NE/SW/SE Sec. 35 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3677

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Glen Pipe Pulling Co

Address Box 156 Ellinwood, KS License No. 686

Operation Completed: Hour 11:00 AM Day 1 Month 2 Year 1974

The above well was plugged as follows:

290 ft 8 5/8 surface cement circulated. 3677 ft 5 1/2 long string  
cemented with 175 sacks. Top perf. 3365 ft. Plug at 3300 ft. Sand  
& 5 sacks cement with bailer. Pulled 2624 ft 5 1/2. Pump 2 sacks hulls,  
10 sacks gel, 100 sacks cement to surface.

Pumped by Halliburton Cementing Co Great Bend, KS

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 4 1974  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

DATE 2/5/74  
INV. NO. 8514-W

Signed: [Signature]  
Well Plugging Supervisor