

15.185.01822.0000

Form GP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

5-6-65

RECEIVED
STATE CORPORATION COMMISSION

MAY 6 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Socony Mobil Oil Company, Inc.

Complete Address: 300 N. Broadway, Wichita, Kansas

Lease Name R. C. Gates Well No. # 1

Location NW NW NW Sec. 35 Twp. 21 Rge. 13 (E) W

County Stafford Total Depth 3658'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 2:00PM Day 5th Month May Year 1965

The Above well was plugged as follows:

255' of 13 3/8" surface pipe, cement circulated. 3657' of 7" long
string, cemented with 300 sacks. Plug back to 3525'. Top perferation
3317'. Bottom of the hole was sanded to 3290', and cemented with 5
sacks. 800' of 7" long string was recovered from the hole. Hole was
filled with mud to 255', and 10' of rock bridge, and cemented with 50
sacks. Hole was filled with mud to 40', and 10' of rock bridge, and
cemented with 25 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/6/65

INV. NO. 1109-W

Signed: Archie Elving
Well Plugging Supervisor